

PAVEMENT MARKING SCHEDULE											REMARKS
STATION	STATION	LOCATION	PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID				GROOVING FOR RECESSED PAVEMENT				
			LETTERS AND SYMBOLS	LINE 4"	LINE 5"	LINE 12"	MARKING, LETTERS, NUMBERS AND SYMBOLS	MARKING 5"	MARKING 6"	MARKING 13"	
			(SQ FT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(FOOT)	(FOOT)	(FOOT)	
180+70.00		LT	41.5				41.5				LANE DROP ARROW
189+70.00		LT	41.5				41.5				LANE DROP ARROW
169+30.00	177+70.00	LT		840.0							N.B. INSIDE EDGE LINE (SOLID)
166+55.00	1476+00.00	LT		26409.0							N.B. INSIDE EDGE LINE (SOLID)
226+30.00	231+50.00	LT		520.0							N.B. OUTSIDE EDGE LINE (SOLID)
166+50.00	172+50.00	RT		600.0							S.B. INSIDE EDGE LINE (SOLID)
166+50.00	409+51.00	RT		24149.0							S.B. INSIDE EDGE LINE (SOLID)
224+95.00	230+74.00	RT		579.0							S.B. OUTSIDE EDGE LINE (SOLID)
169+30.00	189+40.00	LT						2010			N.B. INSIDE EDGE LINE (SOLID)
227+97.10	228+96.26	LT						99			N.B. INSIDE EDGE LINE (SOLID)
1465+00.00	1476+00.00	LT						1100			N.B. INSIDE EDGE LINE (SOLID)
228+24.97	229+24.13	LT						99			N.B. OUTSIDE EDGE LINE (SOLID)
166+50.00	186+00.00	RT						1950			S.B. INSIDE EDGE LINE (SOLID)
227+53.74	228+52.30	RT						99			S.B. INSIDE EDGE LINE (SOLID)
403+50.00	409+51.00	RT						601			S.B. INSIDE EDGE LINE (SOLID)
227+25.87	228+25.03	LT						99.0			S.B. OUTSIDE EDGE LINE (SOLID)
226+30.00	231+50.00	LT			130						N.B. INSIDE, CENTER-OUTSIDE (SKIP-DASH)
186+70.00	1476+00.00	LT			6170						N.B. INSIDE, CENTER-INSIDE (SKIP-DASH)
224+95.00	230+74.00	RT			150						S.B. INSIDE, CENTER-OUTSIDE (SKIP-DASH)
172+50.00	409+51.00	RT			5890						S.B. INSIDE, CENTER-INSIDE (SKIP-DASH)
186+70.00	226+30.00	LT							990		N.B. INSIDE, CENTER-INSIDE (SKIP-DASH)
231+50.00	1476+00.00	LT							5050		N.B. INSIDE, CENTER-INSIDE (SKIP-DASH)
172+50.00	224+95.00	RT							1310		S.B. INSIDE, CENTER-INSIDE (SKIP-DASH)
230+74.00	409+51.00	RT							4430		S.B. INSIDE, CENTER-INSIDE (SKIP-DASH)
166+50.00	172+50.00	RT				243					30' SPACING
169+30.00	177+70.00	LT				173					30' SPACING
178+13.05	180+85.86	LT				34					N.B. BRIDGE STRIPEOUT
TOTALS			83	53,097	12340	450	83	6,057	11,780	34	

PAVEMENT MARKING REMOVAL					REMARKS
STATION / LOCATION			PAVEMENT MARKING REMOVAL		
STA.	STA.	LOC.	(SQ FT)		
169+30.00	209+50.00	LT	1340	Northbound Inside Edge Line (Solid):	
209+51.00	226+30.00	LT	560	"	
231+50.00	347+05.54	LT	3856	"	
348+47.10	419+77.93	LT	2377	"	
1461+04.83	1465+00.00	LT	132	"	
178+13.05	180+85.86	LT	68	Northbound Bridge Stripeout (4 stripes at 17')	
166+50.00	209+50.00	RT	1433	Southbound Inside Edge Line (Solid):	
209+51.00	224+95.00	RT	515	"	
230+74.00	347+05.54	RT	3873	"	
348+47.10	403+50.00	RT	1834	"	
177+71.13	180+49.29	RT	34.0	Southbound Bridge Stripeout (2 stripes at 17')	
TOTALS			16,022		

PAVEMENT REMOVAL						REMARKS
STATION / LOCATION		PAVEMENT REMOVAL	HOT MIX ASPHALT SURFACE REMOVAL - 1 1/2"	PAVED SHOULDER REMOVAL		
STATION	TO	STATION	(SQ YD)	(SQ YD)	(SQ YD)	
226+30.00	-	228+55.75	593.9			NORTHBOUND
228+74.78	-	231+50.00	728.7			"
224+95.00	-	227+74.49	743.9			SOUTHBOUND
227+94.02	-	230+74.00	752.9			"
196+33.00	-		501.7			CROSSOVER
305+90.00	-		486.1			"
409+20.00	-		253.9			"
169+30.00	-	178+13.05		1177.4		NORTHBOUND
180+85.86	-	192+00.00		1485.5		"
1465+00.00	-	1476+00.00		1466.7		"
166+50.00	-	177+71.30		1495.1		SOUTHBOUND
180+49.21	-	189+00.00		1134.4		"
403+50.00	-	409+51.00		801.3		"
226+30.00	-	228+62.98			245.9	NB OUTSIDE
228+93.65	-	231+50.00			329.9	"
224+95.00	-	227+52.00			285.1	SB OUTSIDE
227+90.00	-	230+74.00			296.2	"
189+50.00	-	194+50.00			541.8	NB INSIDE
194+50.00	-	228+36.90			2294.6	"
228+70.68	-	1465+00.00			14047.8	"
189+00.00	-	192+50.00			382.0	SB INSIDE
192+50.00	-	227+75.00			2297.0	"
228+12.00	-	403+50.00			12614.2	"
TOTALS			4,061	7560	33,335	