

PAY ITEM	ITEM	UNIT	TOTAL QUANTITY	SRTS FUNDS	
				100% FEDERAL	0021 SAFETY URBAN
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	2050		2050
25000200	SEEDING, CLASS 2	ACRE	0.43	0.43	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	39	39	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	39	39	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	39	39.00	
25100630	EROSION CONTROL BLANKET	SQ YD	2050	2050	
28000400	PERIMETER EROSION BARRIER	FOOT	610	610	
28000510	INLET FILTERS	EACH	5	5	
* 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	24000	24000	
42400800	DETECTABLE WARNINGS	SQ FT	300	300	
44000560	COMBINATION CURB AND GUTTER REMOVAL	FOOT	22	22	
44000600	SIDEWALK REMOVAL	SQ FT	5825	5825	
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	5	5	
* 54200217	PIPE CULVERTS, CLASS C, TYPE 1 12"	FOOT	41	41	
* 54200223	PIPE CULVERTS, CLASS C, TYPE 1 18"	FOOT	50	50	
54215547	METAL END SECTIONS 12"	EACH	2	2	
54215553	METAL END SECTIONS 18"	EACH	3	3	
55100500	STORM SEWER REMOVAL 12"	FOOT	15	15	
55100900	STORM SEWER REMOVAL 18"	FOOT	34	34	
60288600	VALVE BOXES TO BE ADJUSTED	EACH	3	3	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	22	22	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUB	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
~ 72000100	SIGN PANEL - TYPE 1	SQ FT	100	100	
~ 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	240	240	
~ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	650	650	
~ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	500	500	
~ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	70	70	
~ 78001130	PAINT PAVEMENT MARKING - LINE 12"	FOOT	50	50	
~ 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	15	15	
* Z0004002	BOLLARDS	EACH	3	3	
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	

* INDICATES SPECIAL PROVISION
 ~ INDICATES SPECIALTY ITEM