SIGN LEGEND

1 — W11-2 FLORESCENT YELLOW GREEN 36" x 36"

2 — W16-9P FLORESCENT YELLOW GREEN 24" x 12" — AHEAD

3 — R1-1 30" x 30" — STOP

LEGEND

- PCC SIDEWALK, 5"
- DETECTABLE WARNING
- SIGN
- PIPE CULVERT

N

20 0 20
SCALE IN FEET

REDBIRD LANE

COLUMBIA STREET

THERMO. PAVEMENT MARKING LINE, WHITE, 6", 582 LF

PCC SIDEWALK, 5" 4673 SF

RESTORATION AREA, 66 SQ YD

RESTORATION AREA, 73 SQ YD

RESTORATION AREA, 4 SQ YD

THERMO. PAVEMENT MARKING LINE, WHITE, 12", 66 LF

PCC SIDEWALK, 5" 30 SF

DETECTABLE WARNINGS, 12 SF

THERMO. PAVEMENT MARKING LINE, WHITE, 24", 14 LF

PROJECT ENDS STA 404+55.33

PIPE CULVERT, 18" 13 LF N INV = 634.20 S INV = 634.22

RESTORATION AREA, 8 SQ YD

DETECTABLE WARNINGS, 26 SF

FOR IMPROVEMENTS ALONG COLUMBIA ST SEE 20

PROJECT BEGINS STA 400+00.00

+00.0 17.5 LT
+00.0 7.2 LT
±15.0 5.0 LT
400+00
+00.0 2.8 RT
±15.0 5.0 RT

"DWIGHT SCHOOL"

EXISTING AND PROPOSED PROFILE AT BASELINE

400+00	400+50	401+00	401+50	402+00	402+50	403+00	403+50	404+00	404+50	405+00
637.70	637.46	637.83	637.74	637.62	637.58	637.56	637.58	637.54	637.48	637.31	637.17	637.04	636.86	636.68	636.56	636.47	636.31	635.61	636.11	635.66

640 635 630 625

FILE NAME = X:\Delrigh\d0892392\800324\Civil\MPP2-R32.dgn	USER NAME = CMCCOLLOM	DESIGNED - CJM	REVISED -	
		DRAWN - CJM	REVISED -	
	PLOT SCALE = 20'	CHECKED - REH	REVISED -	
	PLOT DATE = 2/7/2013	DATE - 02/08/13	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PLAN AND PROFILE
REDBIRD LANE

SCALE: 20' | SHEET NO. 2 OF 8 SHEETS | STA. 400+00.00 TO STA. 406+51.39

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	12-00051-00-SW	LIVINGSTON	40	18
		CONTRACT NO. 87547		
	ILLINOIS FED. AID PROJECT			