

SUMMARY OF QUANTITIES				CONSTRUCTION CODE		0021	0021
CODE NO.	BASE BID PAY ITEMS	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS		
Δ* 40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	6	6			
Δ* 42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	164	164			
Δ 44000600	SIDEWALK REMOVAL	SQ FT	164	164			
67100100	MOBILIZATION	L SUM	1	1			
* 81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	49		49		
* 81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	51		51		
* 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	106		106		
* 81028360	UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	66		66		
* 81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	65		65		
* 81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	146		146		
* 81028740	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 1 1/2"	FOOT	360		360		
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	3		3		
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1		1		
* 81500120	GULFBOX JUNCTION, COMPOSITE CONCRETE	EACH	6		6		
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1120		1120		
* 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1		
* 86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1		1		
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	1300		1300		
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	150		150		
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	710		710		
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	1730		1730		
* 87301515	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18 3 PAIR	FOOT	1330		1330		
* 87301804	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 1C	FOOT	80		80		
* 87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	570		570		
* 87500600	TRAFFIC SIGNAL POST, 10 FT.	EACH	3		3		
* 87501000	TRAFFIC SIGNAL POST, 14 FT.	EACH	3		3		
* 87501200	TRAFFIC SIGNAL POST, 16 FT.	EACH	1		1		
* 87600100	PEDESTRIAN PUSH-BUTTON POST, TYPE I	EACH	3		3		
* 87702850	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 24 FT.	EACH	1		1		
* 87702890	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 32 FT.	EACH	2		2		
* 87702900	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 34 FT.	EACH	1		1		
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	21		21		
* 87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4		
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	54		54		
* 88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4		4		
* 88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4		4		

* SEE SPECIAL PROVISIONS

SUMMARY OF QUANTITIES				CONSTRUCTION CODE		0021	0021
CODE NO.	BASE BID PAY ITEMS	UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS		
* 88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	4		4		
* 88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	8		8		
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	8		8		
* 88600100	DETECTOR LOOP, TYPE I	FOOT	660		660		
* 88700200	LIGHT DETECTOR	EACH	2		2		
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		1		
* 89502380	REMOVE EXISTING HANDHOLE	EACH	2		2		
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9		9		
* X0321973	MODIFY EXISTING SERVICE INSTALLATION	EACH	1		1		
* X0323713	RADIO INTERCONNECT SYSTEM COMPLETE, LOCAL	EACH	1		1		
* X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1		1		
* X8250215	PHOTOCELL CONTROL SYSTEM	EACH	1		1		
* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3C, TWISTED, SHIELDED	FOOT	280		280		
* X8760200	ACCESSIBLE PEDESTRIAN SIGNALS	EACH	8		8		
* X8760250	VIBROTACTILE FEATURE	EACH	8		8		
* X8850106	INDUCTIVE LOOP DETECTOR, RACK MOUNTED	EACH	9		9		
Δ* XX005665	REMOVE AND RESET BRICK PAVERS	SQ FT	16	16			
* XX005703	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT, SPECIAL	L SUM	1		1		
* XX007797	LUMINAIRE (SPECIAL)	EACH	3		3		
* Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1		

* SEE SPECIAL PROVISIONS

Δ SPECIALTY ITEMS

FILE NAME = p:\U0070061_Urbana - Main Street HSP\Plans\sheet04 summary.dgn
 PLOT DATE = 1/18/2013 8:58:16 AM

DESIGNED - JAJ	REVISED -
DRAWN - JAJ	REVISED -
CHECKED - SMW	REVISED -
DATE - 01/20/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 4 OF 12 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7124	11-00510-00-TL	CHAMPAIGN	12	4
MAIN STREET		CONTRACT NO. 91481		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		