SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE: 80% FEDERAL 20% STATE SN 059-3329 0011					
20200100	EARTH EXCAVATION	CU YD	235	235					
20300100	CHANNEL EXCAVATION	CU YD	100	100					
20400800	FURNISHED EXCAVATION	CU YD	2,955	2,955					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	38	38					
28000305	TEMPORARY DITCH CHECKS	FOOT	136	136					
28000400	PERIMETER EROSION BARRIER	FOOT	483	483					
28000500	INLET AND PIPE PROTECTION	EACH	2	2					
28100207	STONE RIPRAP, CLASS A4	TON	240	240					
28200200	FILTER FABRIC	SQ YD	253	253					
35100100	AGGREGATE BASE COURSE, TYPE A	TON	990	990					
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	73	73					
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	622	622					
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	251	251					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	166	166					

* SPECIAL PROVISION

935995