

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED 20% STATE 0005		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	11.5	11.5		
20800150	TRENCH BACKFILL	CU YD	5	5		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	214	214		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	14877	14877		
40600300	AGGREGATE (PRIME COAT)	TON	298	298		
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	5450	5450		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	1220	1220		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	900	900		
40600990	TEMPORARY RAMP	SO YD	180	180		
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	394	394		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10938	10938		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED 20% STATE 0005		
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	1558	1558		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	296	296		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	343	343		
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	7669	7669		
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SO YD	8238	8238		
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SO YD	2811	2811		
44000300	CURB REMOVAL	FOOT	22	22		
44004250	PAVED SHOULDER REMOVAL	SO YD	1367	1367		
44201811	CLASS D PATCHES, TYPE I, 14 INCH	SO YD	20	20		
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	2311	2311		
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SO YD	477	477		
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SO YD	1170	1170		
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	4021	4021		

FILE NAME :	USER NAME : steffennk	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pvidot\stefennk\00263610\07	44977-shr-soq.dgn	DRAWN -	REVISED -		332	(16.17,18)RS-2	LAWRENCE	40	4			
PLOT SCALE : 100.0000 / in.	CHECKED -	REVISED -	REVISED -		SCALE: NA			SHEET NO. 1 OF 4 SHEETS		STA.	TO STA.	ILLINOIS FED. AID PROJECT
PLOT DATE : 10/15/2012	DATE -	REVISED -	REVISED -		CONTRACT NO. 94977							