

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED 20% STATE 0005		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4	4		
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	13778	13778		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	47	47		
70300220	TEMPORARY PAVEMENT MARKING LINE 4"	FOOT	111038	111038		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	260	260		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1531	1531		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	47	47		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED 20% STATE 0005		
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	260	260		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	111038	111038		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	565	565		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
X0322936	REMOVE EXISTING FLARED END SECTION	EACH	2	2		
* X2501000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.5	0.5		
X4060995	TEMPORARY RAMP, SPECIAL	SO YD	156	156		
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	128475	128475		
X4421000	PARTIAL DEPTH PATCHING	TON	1242	1242		
X4422000	PARTIAL DEPTH REMOVAL (VARIABLE DEPTH)	SO YD	3170	3170		
X6061005	CONCRETE CURB, TYPE B (SPECIAL)	FOOT	27	27		
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	17	17		