

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SHEET INDEX AND SUMMARY OF QUANTITIES
3	SAFETY PLAN
4	TYPICAL SECTIONS AND PAVEMENT DETAILS
5	ALIGNMENT DATA AND PAVEMENT LAYOUT
6	STORM WATER POLLUTION PREVENTION PLAN
7	STORM WATER POLLUTION DETAILS
8	REMOVAL PLAN
9	PLAN & PROFILE - TAXIWAY
10	PLAN & PROFILE - HAUL ROAD
11	PLAN & PROFILE - HAUL ROAD
12	TAXIWAY AND APRON CROSS SECTIONS
13	TAXIWAY AND APRON CROSS SECTIONS
14	HAUL ROAD CROSS SECTIONS
15	HAUL ROAD CROSS SECTIONS
16	HAUL ROAD CROSS SECTIONS
17	GRADING PLAN
18	JOINTING PLAN
19	JOINTING DETAILS
20	DRAINAGE SCHEDULES
21	UNDERDRAIN AND DRAINAGE DETAILS
22	UNDERDRAIN AND DRAINAGE DETAILS
23	FENCING PLAN
24	FENCING NOTES AND DETAILS
25	FENCING NOTES AND DETAILS
26	REFLECTIVE MARKER AND ELECTRICAL PLAN
27	ELECTRICAL DETAILS
28	ELECTRICAL DETAILS
29	ELECTRICAL NOTES SHEET 1
30	ELECTRICAL NOTES SHEET 2
31	MARKING PLAN
32	LANDSCAPING PLAN

SUMMARY OF QUANTITIES - BASE BID

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR108158	1/C #8 5 KV UG CABLE IN UD	L.F.	275.0	
AR108960	REMOVE CABLE	L.F.	66.0	
AR110504	4-WAY CONCRETE ENCASED DUCT	L.F.	41.0	
AR125100	ELEVATED RETROREFLECTIVE MARKER	EACH	13.0	
AR125901	REMOVE STAKE MOUNTED LIGHT	EACH	1.0	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1.0	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	3,680.0	
AR156510	SILT FENCE	L.F.	1,146.0	
AR156520	INLET PROTECTION	EACH	5.0	
AR162510	CLASS E FENCE 10'	L.F.	154.0	
AR162900	REMOVE CLASS E FENCE	L.F.	200.0	
AR209604	CRUSHED AGGREGATE BASE COURSE - 4"	S.Y.	2,280.0	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	12,109.0	
AR401660	SAW & SEAL BITUMINOUS JOINTS	L.F.	54.0	
AR401665	BITUMINOUS PAVEMENT SAWING	L.F.	712.0	
AR501506	6" PCC PAVEMENT	S.Y.	2,205.0	
AR501530	PCC TEST BATCH	EACH	1.0	
AR501900	REMOVE PCC PAVEMENT	S.Y.	1,254.0	
AR620520	PAVEMENT MARKING - WATERBORNE	S.F.	1,160.0	
AR620525	PAVEMENT MARKING - BLACK BORDER	S.F.	169.0	
AR701512	12" RCP, CLASS IV	L.F.	106.0	
AR705506	6" PERFORATED UNDERDRAIN	L.F.	349.0	
AR705640	UNDERDRAIN CLEANOUT	EACH	4.0	
AR751411	INLET - TYPE A	EACH	1.0	
AR751927	REPLACE FRAME & GRATE	EACH	1.0	
AR752412	PRECAST REINFORCED CONC. FES 12"	EACH	4.0	
AR800423	BIT. MILLINGS, 24"	S.Y.	2,057.0	
AR800589	BIT. MILLINGS SUBBASE, 6"	S.Y.	2,280.0	
AR901510	SEEDING	ACRE	6.4	
AR905510	TOPSOILING (FROM ON SITE)	C.Y.	2,464.0	
AR905520	TOPSOILING (FROM OFF SITE)	C.Y.	1,108.0	
AR908510	MULCHING	ACRE	6.4	

SUMMARY OF QUANTITIES - ADDITIVE ALTERNATE NO. 1

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AS501900	REMOVE PCC PAVEMENT	S.Y.	1,557.0	
AS901510	SEEDING	ACRE	0.5	
AS905520	TOPSOILING (FROM OFF SITE)	C.Y.	276.0	
AS908510	MULCHING	ACRE	0.5	

REVISION	DATE

MT. VERNON AIRPORT



MT. VERNON, ILLINOIS

IL PROJ.: MW-4197

SBG PROJ.: 3-17-0074-BZ

Hanson Project No.	12A0044D	LAYOUT	LDH	12/13/12
File Name	02-G-002-FLP.dwg	DRAWN	LDH	12/13/12
Scale	N/A	REVIEWED	BSS	2/21/13
Date	3/1/13			



© Copyright Hanson Professional Services Inc. 2013
Hanson Professional Services Inc.
 1622 South Sixth Street
 Springfield, Illinois 62703-2886

CONSTRUCT APRON AND TAXIWAY IN SOUTH FRONTAL AREA

SHEET INDEX AND SUMMARY OF QUANTITIES

FEB 21, 2013 11:54 AM H:\USM0682
 p:\s\sp\sw306\hanson.com\hanson_projects\Documents\12A0044\12A0044D\CAD\Airport\Sheet\G-002-FLP