



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 17, 2019

SUBJECT: FAP Route 304 (IL 96)  
Project STP-SLGR(785)  
Section 6B-3  
Calhoun County  
Contract No. 76J17  
Item No. 99, April 26, 2019 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices in iCX
2. Revised page 8 of the Special Provisions
3. Revised sheets 4,9,12,15,16,26 and 41 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.  
Bureau Chief  
Bureau of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

CWR/cr

**TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL)**

This work shall be done in accordance with Section 631 of the Standard Specifications except for the following. The terminal shall be provided with a 17' radius and the posts along the approach slab shall be 9' long. The Contractor shall field check the radius prior to ordering materials.

Basis of Payment: This work will be paid for at the contract unit price per each for TRAFFIC BARRIER TERMINAL, TYPE 6 (SPECIAL).

**TRAFFIC CONTROL PLAN**

Effective: July 12, 1993

Revised: May 12, 1997

Traffic control shall be in accordance with the applicable sections of the "Standard Specifications for Road and Bridge Construction", the applicable guidelines contained in the "National Manual on Uniform Traffic Control Devices for Streets and Highways", Illinois Supplement to the National Manual of Uniform Traffic Control Devices, these Special Provisions, and any special details and Highway Standards contained herein and in the plans.

Special attention is called to Articles 107.09 and 107.14 of the "Standard Specifications for Road and Bridge Construction" and the following Highway Standards relating to traffic control:

701001	701006	701301	701311	701321	701501
701901	704001				

In addition, the following Special Provision(s) will also govern traffic control for this project:

Construction and Maintenance Sign Supports  
Traffic Control and Protection, Standard 701321 (Special)

**TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)**

This work shall be done in accordance with the applicable portions of Section 700 of the Standard Specifications and Highway Standard 701321. Standard 701321 shall be modified to fit the existing site conditions as shown on the plans. Additional signals to maintain access to entrances shall be required as well as additional signs. The Engineer shall determine the exact layout required for the stage construction. Additional barricades, temporary concrete barrier, portable traffic signals, and signs may be required in addition to those shown in the plans. Temporary rumble strips shall not be used due to the residential area.

Basis of Payment: This work will be paid for at the contract unit price per each for TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL).

Revised 4-17-19