

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

Various Routes  
OVD SIN STR REP & REPL 2007-16  
Various Counties  
Sheet 6 of 51  
Contract Number 44949

District 5  
Overhead Sign Structure Replacement

Location No.:		State I.D. No.:		5S010I057R236.24	
County:	Champaign	Route:	I - 57	M.P.:	236.24
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE-SPAN, TYPE I A		FOOT	90.00		
DRILLED SHAFT CONCRETE FOUNDATION		CU YD	25.40		
REMOVE CONCRETE FOUNDATION-OVERHEAD		EACH	2.00		
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE		EACH	2.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	214.00		
REMOVE & REINSTALL WALKWAY		SQ FT	31.00		
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00		
REPAIR HANDRAIL LOCKING PIN CONNECTION		EACH	8.00		
IMPACT ATTENUATORS, RELOCATE (NON-DIRECTIVE) TL3		EACH	2.00		
GUARD POSTS		EACH	20.00		
GUARD POSTS REMOVAL		EACH	10.00		
This overhead sign structure is being completely replaced.					

Location No.:		State I.D. No.:		5S010I057L238.44	
County:	Champaign	Route:	I - 57	M.P.:	238.44
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE SPAN, TYPE I A		FOOT	88.00		
DRILLED SHAFT CONCRETE FOUNDATION		CU YD	23.40		
REMOVE CONCRETE FOUNDATION OVERHEAD		EACH	2.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	375.00		
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00		
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE		EACH	2.00		
REPLACE OVERHEAD SIGN WALKWAY		FOOT	35.00		
IMPACT ATTENUATORS, RELOCATE (NON-DIRECTIVE) TL3		EACH	2.00		
GUARD POSTS		EACH	20.00		
GUARD POSTS REMOVAL		EACH	15.00		
REPLACE / TIGHTEN CLIP PER SIGN		EACH	3.00		
This overhead sign structure is being completely replaced.					

Location No.:		State I.D. No.:		5C010U045R012.76	
County:	Champaign	Route:	U.S. - 45	M.P.:	12.76
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE-CANTILEVER TYPE III A		FOOT	40.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	128.00		
REMOVE & REINSTALL WALKWAY		FOOT	53.50		
REPLACE / TIGHTEN CLIP PER SIGN		EACH	2.00		
REPAIR HANDRAIL LOCKING PIN CONNECTION		EACH	8.00		
IMPACT ATTENUATORS, (NON-DIRECTIVE) TL3		EACH	1.00		
REMOVE CONCRETE FOUNDATION OVERHEAD		EACH	2.00		
DRILLED SHAFT CONCRETE FOUNDATION		CU YD	12.50		
This overhead sign structure is being replaced with an overhead sign structure cantilever, Type III.					

Location No.:		State I.D. No.:		5S010I074R179.10	
County:	Champaign	Route:	I - 74	M.P.:	179.10
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE-SPAN TYPE I A		FOOT	84.00		
DRILLED SHAFT CONCRETE FOUNDATION		CU YD	20.40		
REMOVE CONCRETE FOUNDATION-OVERHEAD		EACH	2.00		
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE		EACH	2.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	253.00		
REMOVE & REINSTALL WALKWAY		FOOT	50.00		
RELOCATE ELECTRIC SERVICE		EACH	1.00		
DISCONNECT/RECONNECT ELECTRIC SERVICE		EACH	1.00		
REPLACE OVERHEAD SIGN WALKWAY		FOOT	17.00		
GUARDRAIL REMOVAL		FOOT	50.00		
GUARDRAIL MARKERS, TYPE A		EACH	1.00		
STEEL PLATE BEAM GAURDRAIL, TYPE B		FOOT	50.00		
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00		
REPAIR HANDRAIL LOCKING PIN CONNECTION		EACH	8.00		

Location No.:		State I.D. No.:		5S092I074R213.40	
County:	Vermilion	Route:	I-74	M.P.:	213.4
Description of Work		Unit	Quantity		
REMOVE OVERHEAD SIGN STRUCTURE-SPAN		EACH	1.00		
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II A		FOOT	64.00		
STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE		EACH	2.00		
REMOVE & REINSTALL SIGN PANEL		SQ FT	26.00		
REMOVE & REINSTALL WALKWAY		FOOT	43.00		
DRILLED SHAFT CONCRETE FOUNDATION		CU YD	14.50		
REMOVE CONCRETE FOUNDATION OVERHEAD		EACH	2.00		
FURNISH & INSTALL SAFETY CHAIN		EACH	2.00		
DISCONNECT/RECONNECT ELECTRIC SERVICE		EACH	1.00		
RELOCATE ELECTRIC SERVICE		EACH	1.00		
GUARDRAIL REMOVAL		FOOT	50.00		
GUARDRAIL MARKERS, TYPE A		EACH	3.00		
STEEL PLATE BEAM GUARDRAIL, TYPE A		FOOT	100.00		
STEEL PLATE BEAM GUARDRAIL, TYPE B		FOOT	50.00		
TBT TYPE 1, SPECIAL (TANGENT)		EACH	1.00		
TERMINAL MARKER-DIRECT APPLIED		EACH	1.00		
STEEL PLATE BEAM GUARDRAIL STEEL POST		EACH	8.00		
SIGN PANEL - TYPE 3		SQ FT	314.25		
REMOVE SIGN PANEL - TYPE 3		SQ FT	265.00		
REPLACE OVERHEAD SIGN WALKWAY		FOOT	6.00		
This overhead sign structure is being completely replaced.					