

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

Various Routes
OVD SIN STR REP & REPL 2007-16
Various Counties
Sheet 40 of 51
Contract Number 44949

District 7
Overhead Sign Structure Replacement

| | | | | | |
|--|-------|-----------------|-----------------|------------|-------|
| Location No.: | 7-01 | State I.D. No.: | 7S058I072R137.1 | | |
| County: | Macon | Route: | 1-72 | M.P.: | 137.1 |
| | | | | Direction: | EB |
| Description of Work | Unit | Quantity | | | |
| REMOVE OVERHEAD SIGN STRUCTURE - SPAN | EACH | 1.00 | | | |
| OVERHEAD SIGN STRUCTURE - SPAN, TYPE I A | FOOT | 89.00 | | | |
| DRILLED SHAFT CONCRETE FOUNDATION | CU YD | 20.40 | | | |
| REMOVE CONCRETE FOUNDATION OVERHEAD | EACH | 4.00 | | | |
| STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE | EACH | 2.00 | | | |
| REMOVE & REINSTALL SIGN PANEL | SQ FT | 155.50 | | | |
| REMOVE & REINSTALL WALKWAY | FOOT | 31.00 | | | |
| FURNISH & INSTALL SAFETY CHAIN | EACH | 2.00 | | | |
| REPAIR HANDRAIL LOCKING PIN CONNECTION | EACH | 6.00 | | | |
| This structure is being completely replaced. | | | | | |
| Design or as built plans for this structure are not available. | | | | | |

| | | | | | |
|--|-------|-----------------|-----------------|------------|-------|
| Location No.: | 7-02 | State I.D. No.: | 7S058I072R138.1 | | |
| County: | Macon | Route: | 1-72 | M.P.: | 138.1 |
| | | | | Direction: | EB |
| Description of Work | Unit | Quantity | | | |
| REMOVE OVERHEAD SIGN STRUCTURE SPAN | EACH | 1.00 | | | |
| OVERHEAD SIGN STRUCTURE - SPAN, TYPE II A | FOOT | 108.00 | | | |
| DRILLED SHAFT CONCRETE FOUNDATION | CU YD | 24.60 | | | |
| REMOVE CONCRETE FOUNDATION OVERHEAD | EACH | 2.00 | | | |
| STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE | EACH | 2.00 | | | |
| REMOVE & REINSTALL SIGN PANEL | SQ FT | 343.00 | | | |
| REMOVE & REINSTALL WALKWAY | FOOT | 63.00 | | | |
| FURNISH & INSTALL SAFETY CHAIN | EACH | 2.00 | | | |
| REPAIR HANDRAIL LOCKING PIN CONNECTION | EACH | 9.00 | | | |
| REPLACE / TIGHTEN CLIP PER SIGN | EACH | 2.00 | | | |
| DISCONNECT / RECONNECT ELECTRIC SERVICE | EACH | 1.00 | | | |
| RELOCATE ELECTRIC SERVICE | EACH | 1.00 | | | |

| | | | | | |
|--|-------|-----------------|------------------|------------|------|
| Location No.: | 7-03 | State I.D. No.: | 7S058U051R000.41 | | |
| County: | Macon | Route: | U. S. 51 | M.P.: | 0.41 |
| | | | | Direction: | NB |
| Description of Work | Unit | Quantity | | | |
| REMOVE OVERHEAD SIGN STRUCTURE - SPAN | EACH | 1.00 | | | |
| OVERHEAD SIGN STRUCTURE - SPAN, TYPE IA | FOOT | 95.00 | | | |
| DRILLED SHAFT CONCRETE FOUNDATION | CU YD | 20.40 | | | |
| REMOVE CONCRETE FOUNDATION OVERHEAD | EACH | 4.00 | | | |
| STRUCTURAL STEEL SUPPORT OVERHEAD SIGN STRUCTURE | EACH | 2.00 | | | |
| REMOVE & REINSTALL SIGN PANEL | SQ FT | 488.00 | | | |
| REMOVE & REINSTALL WALKWAY | FOOT | 49.25 | | | |
| REPLACE / TIGHTEN CLIP PER SIGN | EACH | 3.00 | | | |
| REPAIR HANDRAIL LOCKING PIN CONNECTION | EACH | 8.00 | | | |
| FURNISH & INSTALL SAFETY CHAIN | EACH | 2.00 | | | |
| DISCONNECT / RECONNECT ELECTRIC SERVICE | EACH | 1.00 | | | |
| RELOCATE ELECTRIC SERVICE | EACH | 1.00 | | | |