3" 🛊 Galvanized Steel

Conduit. Thread and cap both ends.

3'-0" ¢

END VIEW

Elevation (Bottom)

Various Routes OVD SIN STR REP & REPL 2007-16 Various Counties Sheet 49 of 51 Contract Number 44949

For anchor rod size and placement, see Support Frame Detail Sheet.

12-#9 v4(E) bars


- Anchor rod shall be ground or filed to bright metal at clamp and cable connection location.

Approved clamps

#6 copper

34" \$ x 10'-0" copper weld ground rod driven into ground 9'-0". Cost of rod, cable, conduit, caps and clamps shall be included in Drilled Shaft Concrete Foundations.

8'-3" € to €



w(E) 24 #9 F less 5" -#4 bar spiral (E) - see Side Elevation

The foundation dimensions shown are based on the presence of mostly cohesive soils with an average Unconfined Compressive Strength (Ou) of at least 1.25 tsf, which must be determined by previous soil investigations at the jobsite. When other conditions are indicated, the boring data will be included in the plans and the foundation dimensions shown will be the result of site specific designs.

If the conditions encountered are different than those indicated, the Contractor shall notify the Engineer to determine if the foundation dimensions need to be modified. If dimensions "B" or "F" are revised by more than 12" by the Contractor, "as-built" plans shall be prepared and submitted to the District Bureau of Operations for future reference.

No sonotubes or decomposable forms shall be used below the lower conduit entrance. Permanent metal forms or other shielding may not be left in place below that elevation without the Engineer's written permission.

Concrete shall be placed monolithically, without construction joints.

Backfill shall be placed per Article 502 of Standard Specification and prior to erection

of support column.

A normal surface finish followed by a Bridge Seat Sealer application will be required on concrete surfaces above the lowest elevation 6" below finished ground line. Cost included in Drilled Shaft Concrete Foundation.

3'-0" ♦ SECTION A-A

3 hoops minimum top and bottom 11'-3" 1'-6" 7/21/2 8'-3"

SIDE ELEVATION

Structure Number	Station	Elevation Top	Left Foundation				Right Foundation				Class Si	
			Elevation Bottom	Α	В	F	Elevation Top	Elevation Bottom	Ä	B	F	Concrete (Cu. Yḍs.)
7S058I072R137.1	674 + 00			3' - 0"	16' - 6"	19' - 6"			3' - 0"	16' - 6"	19′ - 6"	20.40
7S0581072R138.1	727 + 00			3' - 0"	20' - 6"	23' - 6"			3' - 0"	20' - 6"	23' - 6"	24.60
7S058U051R000.41	763 + 00			3' - 0"	16' - 6"	19' - 6"			3' - 0"	16′ - 6"	19′ - 6"	20.40
		ļ	************************		14.							
									_			
					<u> </u>							
									-			
											<u> </u>	<u> </u>

PLAN

OVERHEAD SIGN STRUCTURES DRILLED SHAFT DETAILS

> District 7 Overhead Sign Structure Replacement

DESIGNED .	. 50
CHECKED	EXAMINED
DRAWN -	PASSED ENGINEER OF MIDDLE DESIGN
CHECKED -	ENGINEER OF BRIDGES AND STRUCTURES
754~F3	7/01/2006

3'-0" ¢

NUMBER	REVISION	DATE

3'-0" ø

DETAILS FOR 10" & SUPPORT FRAME TYPE I-A or II-A TRUSS