

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
100	104 RS-8	MCHENRY	22	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		1000	Parking					CODE NO	ITEM		UNIT	1000	Parking			
			100% State	50% State 50% Village								100% State	50% State 50% Village					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	90	90					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	287	287					
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	13	12	1				70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	70	70					
40600300	AGGREGATE (PRIME COAT)	TON	61	60	1				70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	7000	7000					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	9.5	9	0.5				* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	146	146					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	36778	36778					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	164	164					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	850	850					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	52	52					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	287	287					
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	2526	2500	26				* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	70	70					
42001300	PROTECTIVE COAT	SQ YD	70	70					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	275	275					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	30000	29690	310				78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	248	248					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	250	250					X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
44002223	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5 3/4"	SQ YD	120	120					X4067107	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1260	1247	13				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	120	120					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	8	8					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	360	360														
55039700	STORM SEWERS TO BE CLEANED	FOOT	200	200														
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1														
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	9	9														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6														
67100100	MOBILIZATION	L SUM	1	1														
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1														
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1														
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9000	9000														
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	99	99														
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	36778	36778														
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	850	850														

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
IL 47