



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 17, 2007

SUBJECT: FAI Route 80/94
Section 2003-106-LS
Cook County
Contract No. 62699
Item No. 151, April 27, 2007 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised pages 4, 5, 6 & 7 of the Schedule of Prices.
2. Revised page i of the Table of Contents to the Special Provisions.
3. Revised pages 9 & 10 of the Special Provisions.
4. Revised sheets 2, 3, 4A, 5, 7, 8, 9 & 9A of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Eric E. Harm
Interim Bureau Chief
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger' with a small 'P.E.' to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Roger Driskell; Estimates; Design & Environment File

TBW:MS;jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62699

State Job # - C-91-079-04
 PPS NBR - 1-73514-0210
 County Name - COOK--
 Code - 31 - -
 District - 1 - -
 Section Number - 2003-106-LS

Project Number

Route
 FAI 80/94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
C2000524	S-ARONIA MELAN 2'	EACH	65.000				
C2001524	S-CORNUS RACEMOSA 2'	EACH	275.000				
C2004240	S-L BENZ SPICEBUSH 2C	EACH	115.000				
C2007118	S-ROSA JENS MK 18	EACH	36.000				
C2007218	S-ROSA KNOCKOUT 18	EACH	25.000				
C2008718	S-ROSA RUG A-PLN 18	EACH	33.000				
C2009624	S-SAMBUCUS CANAD 2'	EACH	50.000				
C2012448	S-VIBURN LENT 4'	EACH	17.000				
C2012824	S-VIBURN TRIL 2'	EACH	45.000				
C3005924	S-RHUS GLABRA 2'BR	EACH	745.000				
C3006024	S-RHUS TYPHINA 2'BR	EACH	182.000				
D2C01018	E-JUNIP HOR WIL 18C	EACH	25.000				
D2001560	E-JUNIP VIRG 5'	EACH	45.000				
D2003860	E-THUJA OCC TEC 5'	EACH	3.000				
* E20200G1	V-PARTHEN QUINQ 1G	EACH	3,739.000				
* REVISED : APRIL 11, 2007							

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

62699

State Job # - C-91-079-04
 PPS NBR - 1-73514-0210
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 2003-106-LS

Project Number

Route
 FAI 80/94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
* K0026700	TREE CARE	EACH	1,154.000				
* K0026810	SHRUB CARE	EACH	934.000				
* K0026820	VINE CARE	EACH	2,467.000				
K0030450	PERENNIAL PL DAF BULB	UNIT	3.850				
K1004469	PERENNIAL PLANTS P-TY	UNIT	9.000				
K1005465	SELECT MOWING STAKES	EACH	14.000				
MX032651	MULCH PLACEMENT 100	SQ M	1,557.000				
MX032675	PERENNIAL PLANT CARE	SQ M	7,130.000				
MX032680	WEED CONTR PRE-EM GRN	KG	305.000				
MX033189	WEED CONT N SEL/N RES	LITER	32.000				
MX033323	COARSE SAND PLACE 100	SQ M	437.000				
* DELETED							
* DELETED							
M2011300	TREE PRUN 25-250	EACH	29.000				
M2011350	TREE PRUN OVER 250	EACH	25.000				
* REVISED : APRIL 11, 2007							

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62699

State Job # - C-91-079-04
 PPS NBR - 1-73514-0210
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 2003-106-LS

Project Number

Route
 FAI 80/94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
* M2011700	SUPPLE WATERING	UNIT	360.000				
M2113150	TOPSOIL F & P 150	SQ M	4,485.000				
M2114100	COMPOST F & P 100	SQ M	2,719.000				
M2500310	SEEDING CL 4	HA	0.100				
M2500400	NITROGEN FERT NUTR	KG	42.000				
M2500500	PHOSPHORUS FERT NUTR	KG	42.000				
M2500600	POTASSIUM FERT NUTR	KG	42.000				
M2500750	MOWING	HA	95.000				
M2503310	INTERSEED CL 4	HA	0.200				
M2510630	EROSION CONTR BLANKET	SQ M	5,070.000				
M2520110	SODDING SALT TOLERANT	SQ M	1,766.000				
XX006078	T-AMELANCH X GRAND 2	EACH	8.000				
X0301407	PERENNIAL PLT-GAL POT	UNIT	19.500				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
* DELETED							
* REVISED : APRIL 11, 2007							

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 62699

State Job # - C-91-079-04
 PPS NBR - 1-73514-0210
 County Name - COOK- -
 Code - 31 - -
 District - 1 - -
 Section Number - 2003-106-LS

Project Number

Route

FAI 80/94

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
* DELETED							
* 67000500	ENGR FIELD OFFICE B	CAL MO	12.000				
67100100	MOBILIZATION	L SUM	1.000				
70102620	TR CONT & PROT 701501	L SUM	1.000				
70102625	TR CONT & PROT 701606	L SUM	1.000				
70102630	TR CONT & PROT 701601	L SUM	1.000				
* REVISED : APRIL 11, 2007							

TABLE OF CONTENTS

LOCATION OF PROJECT 1
DESCRIPTION OF PROJECT 1
COMPLETION DATE PLUS GUARANTEED WORKING DAYS..... 1
TRAFFIC CONTROL PLAN 2
WORK RESTRICTIONS 3
MAINTENANCE OF TRAFFIC..... 3
CHANGEABLE MESSAGE SIGNS 3
KEEPING THE EXPRESSWAY OPEN TO TRAFFIC 3
FAILURE TO OPEN TRAFFIC LANES TO TRAFFIC 5
CIVIL / LANDSCAPING 5
INSPECTION OF MATERIALS FOR PLANTING 5
SELECTIVE MOWING STAKES 6
GENERAL REQUIREMENTS FOR WEED CONTROL SPRAYING 6
SUPPLEMENTAL WATERING 8
MOWING..... 9
MULCH PLACEMENT FOR EXISTING WOODY PLANTS..... 10
WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE 12
WEED CONTROL, NON-SELECTIVE AND NON-RESIDUAL..... 12
COARSE SAND PLACEMENT 14
PLANTING WOODY PLANTS (MODIFIED) 14
WOODY PLANT CARE..... 17
PERENNIAL PLANT CARE 18
PLANTING PERENNIAL PLANTS..... 19
EROSION CONTROL 21
EROSION AND SEDIMENT CONTROL CALL OUT 21
EROSION AND SEDIMENT CONTROL SCHEDULE 22
SURFACE ROUGHENING 22
EROSION AND SEDIMENT CONTROLS 23
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 31
ERRATA FOR THE 2007 STANDARD SPECIFICATIONS (BDE)..... 39
PAYMENTS TO SUBCONTRACTORS (BDE) 40
REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) 41
SEEDING (BDE) 42
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 43
NOTICE OF INTENT..... 45
STORM WATER POLLUTION PREVENTION PLAN..... 46

Revised 04/17/2007

Basis of Payment. This work will be paid for at the contract unit price per unit of SUPPLEMENTAL WATERING, measured as specified. Payment will include the cost of all water, equipment and labor needed to complete the work as specified.

MOWING

Description: This work shall consist of mowing turf grass areas to a height not more than 75 mm (3 inches). Turf grass shall include only those areas sodded and seeded with Seeding Class 2A as shown on prior roadway reconstruction plans. These plans will be made available at the preconstruction meeting.

Schedule: See the plans for schedule of mowing dates.

Equipment: The Contractor shall keep all mowing equipment sharp and properly equipped for operation along an urban arterial route. The equipment used shall be capable of completely severing all growth at the cutting height and distributing it evenly over the mowed area. Special equipment may be required on steep slopes, in narrow areas, and for trimming around posts, poles, fences, trees, shrubs, seedlings, etc.

Method: All mowing and trimming operations are to proceed in the direction of traffic flow. The cut material shall not be windrowed or left in a lumpy or bunched condition. Additional mowing or trimming may be required to obtain the height specified or to disperse mowed material.

Debris encountered during the mowing operations which hampers the operation or is visible from the roadway shall be removed and disposed of according to Article 202.03. All trimmings, windrowed material, and debris removal must be complete to the satisfaction of the Engineer. Damage to the turf, such as ruts or wheel tracks more than 50 MM (2 inches) in depth, or other plantings or highway appurtenances caused by the mowing or trimming operation shall be repaired at the Contractor's expense.

Method of Measurement: Mowing and trimming will be measured in hectares (acres) of surface area mowed at the completion of each mowing cycle.

Plan quantities are estimates only. Actual quantities will be measured in place. Agreement to plan quantities will not be allowed. Shrub beds or perennial beds within the mowed area that are less than 90 square meters (1000 square feet) will not be subtracted from the area mowed.

Basis of Payment: This work will be paid for at the contract unit price per hectare (acre) for MOWING. Any additional mowing or trimming required to obtain the height specified or to disperse mowed material will be considered as included in the cost of the initial mowing. Payment for mowing and trimming shall include the cost of all material, equipment, labor, removal, disposal and incidentals required to complete the work as specified herein and to the satisfaction of the Engineer.

Revised 04/17/2007

MULCH PLACEMENT FOR EXISTING WOODY PLANTS

This work shall be done in accordance with the applicable portion of Section 253.02 (c) and Section 1081.06 of the Standard Specifications for Road and Bridge Construction.

Revised 04/17/2007