

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	34X-BR	DEKALB	90	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

GENERAL NOTES

Pavement Marking shall be done according to Standard 780001, except all arrows shall be the large size and the distance between yellow no-passing lines shall be 8" not 7" as shown in the detail of typical lane and edge lines.

Earth excavation necessary to construct PCC sidewalk shall be included in the cost of PCC sidewalk 5".

The Contractor shall place a PERMANENT SURVEY MARKER, TYPE II, in the bridge parapet as directed by the Engineer.

The Contractor shall submit to the Engineer a description of location, elevation, and coordinates for each permanent survey marker. The Engineer shall submit this this information to the Survey Crew.

Aggregate Base Course, Type B, for temporary access is provided in the plan quantities and shall be used only as needed when directed by the Engineer.

The Contractor shall be responsible for protecting utility property during construction operations as outlined in Article 107.31 of the Standard Specifications. A minimum of 48 hours advance notice is required for non-emergency work. The JULIE number is 800-892-0123. The following listed utilities located within the project limits or immediately adjacent to the project construction limits are members of JULIE:

Name and Address of Utility	Type	Telephone
Mr. Larry Meyers Commonwealth Edison Company 123 Energy Ave. Rockford IL 61109	Electric	(815)-490-2869
Mr. Gary Kluz Verizon 112 West Elm Street Sycamore IL 60178	Telephone	(815)-895-1515
Mr. Michael Zima DeKalb Sanitary District P.O. Box 624/303 Hollister Ave. DeKalb IL 60115	Sewer	(815)-758-3513
Mr. Scott Stogsdill NICOR Gas Co. 1844 Ferry Road Naperville IL 60563-9600	Gas	(630)-983-8676
Mr. Joel Maurer City of DeKalb 223 South Fourth St., Suite B DeKalb IL 60115	Water	(815)-748-2030

Mr. Dale Peters MediaCom 2506 1/2 Bloomington Streator IL 61364	CATV	(815)-672-5071
--	------	----------------

Mr. Mike Williams Comcast Cable 1430 Sycamore Road DeKalb IL 60115	CATV	(815)-758-3401
---	------	----------------

Following are the known utilities located within the project limits or immediately adjacent to the project construction limits which are not members of JULIE and should be notified individually by the contractor:

Name and Address of Utility	Type	Telephone
Mr. Tom Schaefer IDOT-OTTAWA 700 E. Norris Drive Ottawa IL 61350	GOVT	(815)-434-8446

The applicable portions of Article 105.07 of the Standard Specifications shall apply except for the following: The Contractor shall be responsible to locate the vertical depths of the underground utilities which may interfere with construction operations. This work will not be measured or paid for separately, but shall be considered as included in the unit bid price for the item of construction involved.

Per SB 699 (90 day utility relocation law), once right-of-way is clear to award the project, a notice will be sent to the utility companies instructing them to have their facilities relocated within 90 days. Estimated date relocation complete = Letting Date + 135 days.

Porous Granular Embankment should be uncompacted when used at the ends of integral abutments.

PLOT DATE = 10/24/05
SCALE = AS SHOWN
REFERENCE = AREAS
OPERATOR = SUTHEA

REVISIONS	
NAME	DATE
IDOT REVIEW	10/25/06

ILLINOIS DEPARTMENT OF TRANSPORTATION
GENERAL NOTES

FAP RTE 567 (IL RTE 38)
SECTION 34X-BR
DEKALB COUNTY

SCALE: VERT. _____
HORIZ. _____
DATE 10/24/05

DRAWN BY SUTHEA
CHECKED BY BOTT

COMPUTER FILE NO.
D10800CVR
PROJECT 05198
10/25/06-GSJ

GREENE & BRADFORD, INC.
OF SPRINGFIELD
REGISTERED PROFESSIONAL ENGINEERS
PROFESSIONAL DESIGN FIRM NO. 042-000001
1075 W. STATE ST. SUITE 200
SPRINGFIELD, ILLINOIS 62761-2000
TEL: 217-264-1871 FAX: 217-264-1872