

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	34X-BR	DEKALB	90	11
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

55100500 STORM SEWER REMOVAL 12"

FOOT	LOCATION
6	136+39.2, 24' LT - 136+45.9, 24' LT
7	136+43.9, 26.2' LT - 136+51.8, 25.7' LT
6	139+98, 18' LT - 139+98, 24' LT
7	142+10.2, 26.3' LT - 142+17.6, 26.6' LT
8	142+15, 26.3' RT - 142+23.8, 26.6' RT
34	TOTAL

55100700 STORM SEWER REMOVAL 15"

FOOT	LOCATION
12	142+05, 16' LT - 142+10, 26' LT
12	TOTAL

55100900 STORM SEWER REMOVAL 18"

FOOT	LOCATION
9	136+43.8, 15' LT - 136+45.9, 24' LT
9	TOTAL

55101400 STORM SEWER REMOVAL 30"

FOOT	LOCATION
32	140+27, 17' LT - 140+59, 17' LT
32	TOTAL

55101600 STORM SEWER REMOVAL 36"

FOOT	LOCATION
62	141+43, 14' LT - 142+05, 14' LT
62	TOTAL

56109210 WATER VALVES TO BE ADJUSTED

EACH	LOCATION
1	137+05, 19.5' RT
1	137+30, 36' RT
1	137+38, 27' RT
1	138+00, 36' RT
1	138+72, 33' RT
1	140+12, 20' RT
1	142+75, 33.5' RT
7	TOTAL

60218400 MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID

EACH	LOCATION
1	134+75, 15.39' LT
1	135+33.3, 15.25' LT
1	136+15.7, 15.05' LT
3	TOTAL

60219540 MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE

EACH	LOCATION
1	136+43.9, 31.1' RT
1	142+15.04, 27.5' RT
2	TOTAL

60221100 MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID

EACH	LOCATION
1	137+20, 15.51' LT
1	138+00, 16.06' LT
1	138+70, 16.55' LT
1	140+35, 70' LT
1	141+54.84, 65.29' LT
1	141+75, 27.5' LT
6	TOTAL

60222240 MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE

EACH	LOCATION
1	139+99, 27.5' LT
1	140+24, 27.5' LT
2	TOTAL

60237470 INLETS, TYPE A, TYPE 24 FRAME AND GRATE

EACH	LOCATION
1	134+75, 22.2' LT
1	134+75, 32.2' RT
1	135+33.3, 22.9' LT
1	136+15.7, 24' LT
1	136+46, 24.3' LT
1	137+20, 25.25' LT
1	138+00, 26.25' LT
1	138+70, 27.8' RT
1	138+70, 27.13' LT
1	140+24, 27.5' RT
1	141+70, 27.5' LT
1	141+70, 27.5' RT
1	142+92.08, 27.5' LT
13	TOTAL

60240328 INLETS, TYPE B, TYPE 24 FRAME AND GRATE

EACH	LOCATION
1	135+33.3, 32.1' RT
1	136+15.7, 31.1' RT
1	137+20, 29.75' RT
1	138+00, 28.75' RT
1	139+99, 27.5' RT
1	141+75, 27.5' RT
1	142+10, 27.5' RT
7	TOTAL

60255500 MANHOLES TO BE ADJUSTED

EACH	LOCATION
1	136+43.80, 14.98' LT
1	139+98.01, 17.43' LT
1	142+05.99, 14.19' LT
1	142+92.08, 17.40' LT
4	TOTAL

60500050 REMOVING CATCH BASINS

EACH	LOCATION
1	136+39.18, 23.95' LT
1	136+43.89, 26.18' RT
1	136+45.90, 23.96' LT
1	136+51.77, 25.73' RT
1	139+98.43, 23.89' LT
1	139+99.15, 24.24' RT
1	142+10.15, 26.3' LT
1	142+15.04, 26.38' RT
1	142+17.57, 26.55' LT
1	142+23.75, 26.63' RT
10	TOTAL

PLOT DATE = 2/2/2007
 PLOT SCALE = AS SHOWN
 PLOT SCALE = AS SHOWN
 REFERENCE = #REF#
 OPERATOR = #USER#

REVISIONS	
NAME	DATE
IDOT REVIEW	10/25/06
IDOT REVISIONS	2/01/07

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES

FAP RTE 567 (IL RTE 38)
 SECTION 34X-BR
 DEKALB COUNTY

SCALE: VERT. 1"=20'
 HORIZ. 1"=40'
 DATE 10/24/05

DRAWN BY SUTHEARD
 CHECKED BY BOTT

GREENE & BRADFORD, INC.
 OF SPRINGFIELD

COMPUTER FILE NO. D10800CVR
 PROJECT 05198
 10/25/06-CSJ