

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	34X-BR	DEKALB	90	12
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

60605000 COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.24

FOOT	LOCATION	
568.2	134+70	- 140+38.21 LT
568.2	134+70	- 140+38.21 RT
164.8	141+55.21	- 143+20, LT
164.8	141+55.21	- 143+20, RT
1466	TOTAL	

63000000 STEEL PLATE BEAM GUARD RAIL, TYPE A

FOOT	LOCATION	
12.5	141+44.79, 78.25' LT	- 141+47.02, 72.54' LT
37.5	141+50.08, 72.4' RT	- 141+55.21, 40.5' RT
50.0	TOTAL	

63100085 TRAFFIC BARRIER TERMINAL, TYPE 6

EACH	LOCATION	
1	140+26.68, 74.97' RT	- 140+38.21, 39.5' RT
1	141+47.02, 72.54' LT	- 141+55.21, 39.5' LT
2	TOTAL	

63200310 GUARDRAIL REMOVAL

FOOT	LOCATION	
40	141+46, 70' LT	- 141+48, 30' LT
46	141+48, 34' RT	- 141+50, 80' RT
86	TOTAL	

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH	LOCATION	
1	135+00, CL	
1	143+00, CL	
2	TOTAL	

70300100 SHORT-TERM PAVEMENT MARKING (ST)

FOOT	LOCATION		
680	134+70	- 143+20, LT & REAR MARKING - WHITE	4 APPL.
680	134+70	- 143+20, LT & RETURN LANE - YELLOW	4 APPL.
37	142+83	- 143+20, RT DOTTED LANE LINE - WHITE	4 APPL.
1397	TOTAL		

70300210 TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS

SQ. FT.	LOCATION	
93.6	135+10, 4.5' RT	2 LEFT TURN ARROWS, 3 APPL.
93.6	136+60, 3.0' RT	2 LEFT TURN ARROWS, 3 APPL.
93.6	138+10, 1.0' RT	2 LEFT TURN ARROWS, 3 APPL.
93.6	139+60, CL	2 LEFT TURN ARROWS, 3 APPL.
93.6	142+35, CL	2 LEFT TURN ARROWS, 3 APPL.
46.8	143+80, CL	LEFT TURN ARROW, 3 APPL.
46.8	145+56, CL	LEFT TURN ARROW, 3 APPL.
46.8	142+35, CL	LEFT TURN ARROW, 3 APPL.
608.4	TOTAL	

70300220 TEMPORARY PAVEMENT MARKING - LINE 4" (TP)

FOOT	LOCATION	
660	134+70, 11' LT	- 143+20, 15.5' LT LANE LINE - DASHED WHITE
660	134+70, 21' RT	- 143+20, 16' RT LANE LINE - DASHED WHITE
2439	134+70, CL	- 142+83, 5.3' LT EDGELINE - SOLID YELLOW
2439	134+70, 10' RT	- 142+83, 5.2' RT EDGELINE - SOLID YELLOW
630	134+70, 1.0' RT	- 143+83, 4.3' LT TURN LANE - DASHED YELLOW
630	134+70, 9.0' RT	- 142+83, 4.2' RT TURN LANE - DASHED YELLOW
222	142+83, 5.2' RT	- 143+20, CL TURN LANE - DOUBLE SOLID YELLOW
222	142+83, 5.4' LT	- 143+20, 5.3' LT CENTERLINE - DOUBLE SOLID YELLOW
654	143+20, 5.3' LT	- 144+29, 5.3' LT CENTERLINE - DOUBLE SOLID YELLOW
360	143+20, CL	- 143+80, 5.3' LT TURN LANE - DOUBLE SOLID YELLOW
75	143+20, 16.5' LT	- 144+27, 16.5' LT LANE LINE - DASHED WHITE
75	143+20, 16.5' RT	- 144+27, 16.5' RT LANE LINE - DASHED WHITE
240	145+25, 16.5' LT	- 148+40, 16.5' LT LANE LINE - DASHED WHITE
240	145+25, 16.5' RT	- 148+40, 16.5' RT LANE LINE - DASHED WHITE
1956	145+23, 5.5' RT	- 148+40, 3' LT CENTERLINE - DOUBLE SOLID YELLOW
1110	146+52, 5.5' RT	- 148+36, 5.5' LT TURN LANE - DOUBLE SOLID YELLOW

STAGE 1

190	134+21	- 135+87.5	WHITE
331	135+87.5	- 139+17.5	WHITE
670	135+87.5	- 139+75	YELLOW
566	139+17.5	- 142+00	WHITE
566	139+17.5	- 142+00	YELLOW
184	142+00	- 143+83	WHITE
382	142+00	- 143+83	YELLOW
43	143+83	- 144+25	WHITE
66	143+83	- 144+25	YELLOW
54	144+25	- 144+56	WHITE

STAGE 2

70	134+00	- 134+70	WHITE
331	134+70	- 138+00	WHITE
331	134+70	- 18+00	YELLOW
201	138+00	- 140+00	WHITE
404	138+00	- 140+00	YELLOW
92	140+00	- 142+82.5	WHITE
565	140+00	- 142+82.5	YELLOW
143	142+82.5	- 144+25	YELLOW
17,801	TOTAL		

70300240 TEMPORARY PAVEMENT MARKING - LINE 6"

FOOT	LOCATION	
141	143+80, 5.5' RT	- 144+27, 5.5' RT TURN LANE - SOLID WHITE
165	144+34, 27' RT	- 144+35, 28' LT CROSSWALK - SOLID WHITE
171	144+40, 27' RT	- 144+41, 30' LT CROSSWALK - SOLID WHITE
207	144+40, 27' RT	- 145+09, 27' RT CROSSWALK - SOLID WHITE
180	144+48, 33' RT	- 145+08, 33' RT CROSSWALK - SOLID WHITE
99	144+53, 41' LT	- 144+86, 45' LT CROSSWALK - SOLID WHITE
87	144+56, 48' LT	- 144+84, 51' LT CROSSWALK - SOLID WHITE
162	145+09, 27' RT	- 145+13, 27' LT CROSSWALK - SOLID WHITE
165	145+15, 28' RT	- 145+19, 27' LT CROSSWALK - SOLID WHITE
381	145+25, 5.5' LT	- 146+52, 5.5' LT TURN LANE - SOLID WHITE
1758	TOTAL	

70300260 TEMPORARY PAVEMENT MARKING - LINE 12"

FOOT	LOCATION	
324	144+34, 27' RT	- 144+35, 28' LT CROSSWALK BARS - WHITE
360	144+48, 33' RT	- 145+08, 33' RT CROSSWALK BARS - WHITE
180	144+56, 48' LT	- 144+84, 51' LT CROSSWALK BARS - WHITE
324	145+09, 27' RT	- 145+13, 27' LT CROSSWALK BARS - WHITE
252	146+93	- 148+33 TURN LANE DIAGONALS - YELLOW
1440	TOTAL	

70300280 TEMPORARY PAVEMENT MARKING - LINE 24"

FOOT	LOCATION	
96	144+29, 5' LT	- 144+29, 27' RT STOP BAR - WHITE
96	145+23, 5' RT	- 145+23, 27' LT STOP BAR - WHITE
192	TOTAL	

70301000 WORK ZONE PAVEMENT MARKING REMOVAL

STAGE	SQ. FT.	LOCATION
STAGE I	220	135+87.5 - 139+17.5
	378	139+17.5 - 142+00
	165	142+00 - 143+65
	24	143+65 - 144+47
	85	145+10 - 147+65
STAGE II	220	134+70 - 138+00
	200	138+00 - 140+00
	189	140+00 - 142+82.5
	48	142+82.5 - 144+03
	62	145+10 - 146+03
	79	146+00 - 148+35
	1670	TOTAL

70400100 TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	
300	139+00	- 142+00
300	TOTAL	

70400200 RELOCATE TEMPORARY CONCRETE BARRIER

FOOT	LOCATION	
200	140+00	- 142+00
200	TOTAL	

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

SQ. FT.	LOCATION	
31.2	135+10, 4.5' RT	2 LEFT TURN ARROWS
31.2	136+60, 3.0' RT	2 LEFT TURN ARROWS
31.2	138+10, 1.0' RT	2 LEFT TURN ARROWS
31.2	139+60, CL	2 LEFT TURN ARROWS
31.2	142+35, CL	2 LEFT TURN ARROWS
15.6	143+80, CL	LEFT TURN ARROW
15.6	145+56, CL	LEFT TURN ARROW
15.6	146+52, CL	LEFT TURN ARROW
202.8	TOTAL	

FILE DATE = 2/2/2007  
 FILE NAME = #FILE#  
 PLOT SCALE = #SCALE#  
 REFERENCE = #REF#  
 OPERATOR = #USER#

REVISIONS	
NAME	DATE
IDOT REVIEW	10/25/06
IDOT REVISIONS	12/13/06
IDOT REVISIONS	1/18/07
IDOT REVISIONS	2/01/07

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SCHEDULE OF QUANTITIES**

FAP RTE 567 (IL RTE 38)  
 SECTION 34X-BR  
 DEKALB COUNTY

SCALE: VERT. HORIZ.  
 DATE 10/24/05

DRAWN BY SUTHEARD  
 CHECKED BY BOTT

GREENE & BRADFORD, INC.  
 OF SPECIFIED

COMPUTER FILE NO.  
 D10800CVR

PROJECT 05198  
 10/25/06-GSJ