

# SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	34X-BR	DEKALB	90	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

<b>X0323684</b>	<b>RELOCATE WATER VALVE</b>
	<b>EACH LOCATION</b>
	1 142+78, 38' LT
	1 TOTAL
<b>X0324886</b>	<b>CONDUIT INSTALLED, 1 1/4" DIA., NON-METALLIC</b>
	<b>FOOT LOCATION</b>
	270 134+70, 27' LT - 137+40, 30' LT
	270 137+40, 30' LT - 140+10, 32' LT.
	28 140+10, 32' LT - SN 019-0044
	12 SN 019-0044 - 141+65 - 32' LT
	150 141+65, 32' LT - 143+15 - 32' LT
	730 TOTAL
<b>X0930400</b>	<b>STORM SEWER WATER MAIN 12"</b>
	<b>FOOT LOCATION</b>
	56 134+75 TO 135+33.3, 32.2' RT
	80 135+33.3 TO 136+15.7, 31.1' RT
	27 136+15.7 TO 136+43.9, 31.1' RT
	74 136+43.9 TO 137+20, 29.75' RT
	78 137+20 TO 138+00, 28.75' RT
	68 138+00 TO 138+70, 27.5' RT
	23 139+99 TO 140+24, 27.5' RT
	6 139+99
	3 141+70 TO 141+75, 23.5' RT
	37 141+75 TO 142+15.04, 27.5' RT
	3 142+15.04 RT
	456 TOTAL
<b>X8730402</b>	<b>ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 19 12 PAIR</b>
	<b>FOOT LOCATION</b>
	270 134+70, 27' LT - 137+40, 30' LT
	270 137+40, 30' LT - 140+10, 32' LT.
	28 140+10, 32' LT - SN 019-0044
	118 SN 019-0044
	12 SN 019-0044 - 141+65 - 32' LT
	150 141+65, 32' LT - 143+15 - 32' LT
	848 TOTAL

<b>XX004051</b>	<b>LIGHT POLE, ORNAMENTAL</b>
	<b>EACH LOCATION</b>
	1 135+78.72, 42' LT
	1 136+99.67, 42' LT
	1 138+30.12, 42' LT
	3 TOTAL

<b>XX004716</b>	<b>LUMINAIRE, METAL HALIDE, SPECIAL, TYPE III, 175 WATT</b>
	<b>EACH LOCATION</b>
	2 135+78.72, 42' LT
	2 136+99.67, 42' LT
	2 138+30.12, 42' LT
	6 TOTAL

<b>50800515</b>	<b>BAR SPLICERS</b>
	<b>EACH LOCATION</b>
	21 140+59.60, 62' RT - 140+59.60, 62' LT
	21 TOTAL
	BIKE PATH


<b>Z0030250</b>	<b>IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3</b>
	<b>EACH LOCATION</b>
	1 138+77 - 139+00 (STAGE I)
	1 142+00 - 142+23 (STAGE I)
	2 TOTAL

<b>Z0030350</b>	<b>IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3</b>
	<b>EACH LOCATION</b>
	1 139+77 - 139+00 (STAGE II)
	1 142+00 - 142+23 (STAGE II)
	2 TOTAL

<b>Z0041700</b>	<b>PLUG EXISTING STORM SEWERS</b>
	<b>EACH LOCATION</b>
	1 140+27, 17' LT
	1 142+05, 14.19' LT
	2 TOTAL

PLOT DATE = 2/2/2007  
 FILE NAME = #FILEL#  
 PLOT SCALE = #SCALE#  
 REFERENCE = #REF#  
 OPERATOR = #USERS#

REVISIONS	
NAME	DATE
IDOT REVIEW	10/25/06
IDOT REVISIONS	12/13/06
IDOT REVISIONS	2/01/07

ILLINOIS DEPARTMENT OF TRANSPORTATION	
<b>SCHEDULE OF QUANTITIES</b>	
FAP RTE 567 (IL RTE 38) SECTION 34X-BR DEKALB COUNTY	
SCALE: VERT. HORIZ. DATE 10/24/05	DRAWN BY SUTHEARD CHECKED BY BOTT
 GREENE & BRADFORD, INC. OF SPRINGFIELD REGISTERED PROFESSIONAL ENGINEERS PROFESSIONAL SEAL NO. 00010001 PROFESSIONAL SEAL NO. 00010002 PROFESSIONAL SEAL NO. 00010003 PROFESSIONAL SEAL NO. 00010004 PROFESSIONAL SEAL NO. 00010005	COMPUTER FILE NO. D10800CVR PROJECT 05198 10/25/06-GSJ