

SUMMARY OF QUANTITIES

| | | | | |
|-----------------------------------------------|---------|---------|--------------|-----------|
| CONTRACT NO. 64C02 | | | | |
| F.A.P. RYE | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 549 | 117BR-M | Ogle | 15 | 2 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | | |

100 % State
SFTY-2A

| Pay Code | Item Description | Units | Quantity |
|------------|-----------------------------------------------------|-------|----------|
| 20400800 | FURNISHED EXCAVATION | CU YD | 75 |
| 40300200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 0.2 |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 1 |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 160 |
| 40600990 | TEMPORARY RAMP | SQ YD | 300 |
| 40603310 | HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 | TON | 86 |
| 42001300 | PROTECTIVE COAT | SQ YD | 199 |
| 44000086 | HOT-MIX ASPHALT SURFACE REMOVAL COMPLETE | SQ YD | 106 |
| 48101200 | AGGREGATE SHOULDERS, TYPE B | TON | 50 |
| 50102400 | CONCRETE REMOVAL | CU YD | 3.1 |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 3.6 |
| 50300260 | BRIDGE DECK GROOVING | SQ YD | 186 |
| 50400405 | PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH) | SQ FT | 798 |
| 50500405 | FURNISHING AND ERECTING STRUCTURAL STEEL | POUND | 450 |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 3030 |
| * 50901050 | STEEL RAILING, TYPE SM | FOOT | 107 |
| * 63000000 | STEEL PLATE BEAM GUARD RAIL, TYPE A | FOOT | 375 |
| * 63100087 | TRAFFIC BARRIER TERMINAL, TYPE 6A | EACH | 4 |
| * 63100167 | TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT) | EACH | 4 |
| 63200310 | GUARDRAIL REMOVAL | FOOT | 260 |
| 63500105 | DELINEATORS | EACH | 4 |
| 67100100 | MOBILIZATION | L SUM | 1 |
| 70100100 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701316 | EACH | 2 |

100 % State
SFTY-2A

| Pay Code | Item Description | Units | Quantity |
|----------|---------------------------------------------------------------|-------|----------|
| 70100405 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 | EACH | 1 |
| 70100450 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 | L SUM | 1 |
| 70106500 | TEMPORARY BRIDGE TRAFFIC SIGNALS | EACH | 1 |
| 70300100 | SHORT-TERM PAVEMENT MARKING | FOOT | 64 |
| 70300520 | PAVEMENT MARKING TAPE, TYPE III 4" | FOOT | 2580 |
| 70300570 | PAVEMENT MARKING TAPE, TYPE III 24" | FOOT | 24 |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 535 |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 275 |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 550 |
| 78200400 | GUARDRAIL REFLECTORS | EACH | 4 |
| 78200410 | GUARDRAIL MARKERS, TYPE A | EACH | 16 |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 150 |
| X0301424 | SILICONE JOINT SEALER | FOOT | 33 |
| X0320047 | REMOVAL OF EXISTING PRECAST PRESTRESSED CONCRETE DECK BEAMS | SQ FT | 798 |
| X0320887 | POLYMER CONCRETE | CU FT | 2.4 |
| X5030305 | CONCRETE WEARING SURFACE, 5" | SQ YD | 199 |
| Z0001900 | ASBESTOS BEARING PAD REMOVAL | EACH | 5 |
| 50800515 | BAR SPLICERS | EACH | 64 |
| Z0003700 | BEARING PAD ADJUSTMENT | EACH | 12 |
| Z0017300 | DOWEL REPAIR | EACH | 12 |
| Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 |
| Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 |
| Z0032700 | KEYWAY REPAIR | FOOT | 266 |

* SPECIALTY ITEM

Summary of Quantities
 Illinois Route 72 over Tributary to Mud Creek
 FAP Route 549
 Section 117BR-M
 Ogle County
 Structure No. 071-0068