

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80	(81-1) M-4	ROCK ISLAND	33	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

# SCHEDULE OF QUANTITIES

ITEM NO.	DESCRIPTION	EACH	LOCATION	REMARKS
78201000	TERMINAL MARKER - DIRECT APPLIED	1.0	827+50 TO 833+50	TYPE I SPECIAL TERMINAL
		1.0		
78300100	PAVEMENT MARKING REMOVAL	470.0	1034+25 TO 1048+35	RAMP MAINLINE - RT
		418.7	1034+25 TO 1048+35	RAMP MAINLINE - LT
		216.7	827+50 TO 833+50	ADJACENT TO PROPOSED GUARDRAIL RT
		96.7	1033+00 TO 1035+50	GORE EXIT LT
		153.3	215+00 TO 216+45	GORE EXIT RT
TOTAL		1,355.3		
X0301894	REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE UNDERDRAIN	1.0	1050+60 TO 1050+60	
		1.0		
X0324589	PIPE UNDERDRAIN OUTLET EXTENSION FOR 4" PIPE	1.0	1050+60 TO 1050+60	
		1.0		
XX004096	REMOVE AND RE-INSTALL CONCRETE FLARED END SECTIONS	1.0	1048+05 TO 1048+05	
		1.0		

C 64C30				
EARTH WORK SCHEDULE				
LOCATION	20200100 EARTH EXC (CUT) CU YD	EARTH EXC ADJ SHRINK 25% CU YD	20400800 EMBANK (FILL) CU YD	EARTH WORK BALANCE WASTE (+) SHORTAGE (-) CU YD
RAMP MAINLINE				
1034 + 00 - 1048 + 00	26.4	20	176	-157
MAINLINE GUARD RAIL				
827 + 50 - 831 + 50	80	60	67	-7
TOTAL	106	80	243	-164

PLOT DATE = Thu Jan 25 15:44:23 2007  
 FILE NAME = C:\projects\1287286\1287286.dgn  
 USER NAME = grantpa