



CONTRACT NO. 64C90				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
..51Z..	..G2Y-IJIS-R..	..WINNEBAGO..	..R..	..4..
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

UTILITIES			
NAME	TYPE	TELEPHONE	JULIE MEMBER
MR DAVE SCHACHT COMMONWEALTH EDISON COMPANY 123 ENERGY AVE ROCKFORD, IL 61109	ELECTRIC	630-437-2129	YES 800-892-0123
MR JEREMY SCHNACK AT&T 635 18TH STREET ROCK ISLAND, IL 61201	TELEPHONE	309-793-4456	YES 800-892-0123
MS. CONSTANCE LANE NICOR GAS CO 1844 FERRY RD NAPERVILLE, IL 60563-9600	GAS	630-983-8676	YES 800-892-0123
MR. JOHN MARTIN ROCKFORD WATER DEPARTMENT 425 E STATE ST ROCKFORD, IL 61104	WATER	815-961-3766	NO
MR MICHAEL OLSON ROCK RIVER WATER RECLAMATION DISTRICT P.O. BOX 7480/3333 KISHWAUKEE ROCKFORD, IL 61126-7480	SEWER	815-387-7400	YES 800-892-0123
MR MIKE OWENS INSIGHT COMMUNICATIONS OF ROCKFORD 4450 KISHWAUKEE STREET ROCKFORD, IL 61109	CATV	815-395-8977	YES 800-892-0123

GENERAL NOTES:

- NO SIGNAL WORK WILL BE ALLOWED UNTIL ALL COMPONENTS TO COMPLETE THE PROJECT HAVE ARRIVED ON THE JOB SITE.
- THE EXISTING TRAFFIC SIGNALS SHALL REMAIN IN OPERATING ORDER DURING THE INSTALLATION OF PROPOSED SIGNALS AND PAID FOR AS, MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION, LUMP SUM.
- THE ACTUAL LOCATION OF ALL SIGNAL FOUNDATIONS, HANDHOLES AND TRAFFIC CONTROLLER WILL BE DETERMINED BY THE FIELD ENGINEER.
- ALL TRAFFIC SIGNAL HEAD WILL BE ALIGNED WITH THE CENTER APPROPRIATE LANE OR AS DIRECTED BY THE ENGINEER.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITIES PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE CURRENT STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON- EMERGENCY WORK. THE JULIE NUMBER IS 800-892-0123. THE FOLLOWING LISTED UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS.



1.88" Radius, 0.75" Border, 0.50" Indent, Black on White;

[LEFT] White D 2K;

[ON] White D 2K;

[GREEN] White D 2K;

[ARROW] White D 2K;

[ONLY] White D 2K;

Table of letter and object lefts.

L	E	F	T
9.28	12.36	15.52	18.24

O	N
11.78	15.50

G	R	E	E	N
6.98	10.58	13.98	17.14	20.30

A	R	R	O	W
6.18	10.18	13.58	16.90	20.26

O	N	L	Y
8.22	11.94	15.62	18.34

2 MAST-ARM MOUNTED AND  
2 BRACKET MOUNTED PER INTERSECTION

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCALE: VERT. DATE HORIZ. DRAWN BY CHECKED BY

UTILITIES AND SIGN DETAILS

PLOT DATE: 2/15/2007 11:30:46 AM  
 FILE NAME: \\us20\proj\us20\64c90\us20\_64c90.dgn  
 PLOT SCALE: 1:1  
 USER NAME: JNIN