

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	47RS-12	VERMILION	24	5

## SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAP 332 (US 150)  
 RURAL FOUR-LANE  
 STA. 2627+89  
 TO  
 STA. 2743+00  
 80% FED  
 20% STATE  
 I000

CONSTRUCTION TYPE CODE:

<u>CODE NO</u>	<u>ITEM</u>	<u>UNIT</u>	<u>TOTAL QUANTITY</u>	<u>VERMILION COUNTY</u>
40300602	SEAL COAT AGGREGATE, SPECIAL	TON	77.0	77.0
40300305	POLYMERIZED BITUMINOUS MATERIALS (COVERS <sup>AND</sup> SEAL COATS)	GALLON	8254.0	8254.0
40300600	SEAL COAT AGGREGATE	TON	224.0	224.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	8497.0	8497.0
40600300	AGGREGATE (PRIME COAT)	TON	123.0	123.0
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2579.0	2579.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0	1.0
40600990	TEMPORARY RAMP	SQ YD	78.0	78.0
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	5157.0	5157.0
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	61392.0	61392.0
44201398	CLASS C PATCHES, TYPE I, 14 INCH	SQ YD	12.0	12.0
44201403	CLASS C PATCHES, TYPE II, 14 INCH	SQ YD	168.0	168.0
44201407	CLASS C PATCHES, TYPE III, 14 INCH	SQ YD	16.0	16.0
44201409	CLASS C PATCHES, TYPE IV, 14 INCH	SQ YD	34.0	34.0
67100100	MOBILIZATION	L SUM	1.0	1.0
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1.0	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16576.0	16576.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1842.0	1842.0
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	31.0	31.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	52446.0	52446.0
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	13.0	13.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	568.0	568.0
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	568.0	568.0
X4032500	BITUMINOUS MATERIALS (COVER AND SEAL COATS), SPECIAL	GALLON	2302.0	2302.0
* SPECIALTY ITEMS				