

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	47R5-12	VERMILION	24	9

SCHEDULES OF QUANTITIES

* **40300305 POLYMERIZED BITUMINOUS MATERIALS (COVERS AND SEAL COATS)**

<u>SHOULDERS (A1 SEAL COAT)</u>			<u>LENGTH (FOOT)</u>	<u>WIDTH (FOOT)</u>	<u>AREA (SQ YD)</u>	<u>APPLICATION RATE (GN 403) (GAL/SQ YD) (GALLONS)</u>	
<u>STATION</u>	<u>TO</u>	<u>STATION</u>				<u>(GAL/SQ YD)</u>	<u>(GALLONS)</u>
NB 2627+89.00		NB 2743+00.00	11511.0	8	10232.0	0.35	3581.2
SB 2627+89.00		SB 2743+00.00	11511.0	8	10232.0	0.35	3581.2
						<u>SUB-TOTAL =</u>	<u>7162.4</u>
 <u>SIDE ROADS (A1 SEAL COAT)</u>							
16 TH STREET			30.0	VAR.	928.0	0.35	324.8
TR 900 N (RT 2662+63)			36.0	VAR.	796.0	0.35	278.6
TOWNSHIP ROAD (LT 2665+51.7)			35.0	VAR.	781.0	0.35	273.4
MAPLE GROVE ROAD (LT 2705+41.8)			29.0	VAR.	613.0	0.35	214.6
						<u>SUB-TOTAL =</u>	<u>1091.4</u>
						<u>TOTAL =</u>	<u>8253.8</u>
						<u>USE =</u>	<u>8254.0</u>

* **40300600 SEAL COAT AGGREGATE**

<u>SHOULDERS (A1 SEAL COAT)</u>			<u>LENGTH (FOOT)</u>	<u>WIDTH (FOOT)</u>	<u>AREA (SQ YD)</u>	<u>APPLICATION RATE (GN 403) (LB/SQ YD) (TONS)</u>	
<u>STATION</u>	<u>TO</u>	<u>STATION</u>				<u>(LB/SQ YD)</u>	<u>(TONS)</u>
NB 2627+89.00		NB 2743+00.00	11511.0	8	10232.0	19	97.2
SB 2627+89.00		SB 2743+00.00	11511.0	8	10232.0	19	97.2
						<u>SUB-TOTAL =</u>	<u>194.4</u>
 <u>SIDE ROADS (A1 SEAL COAT)</u>							
16 TH STREET			30.0	VAR.	928.0	19	8.8
TR 900 N (RT 2662+63)			36.0	VAR.	796.0	19	7.6
TOWNSHIP ROAD (LT 2665+51.7)			35.0	VAR.	781.0	19	7.4
MAPLE GROVE ROAD (LT 2705+41.8)			29.0	VAR.	613.0	19	5.8
						<u>SUB-TOTAL =</u>	<u>29.6</u>
						<u>TOTAL =</u>	<u>224.0</u>
						<u>USE =</u>	<u>224.0</u>

* PLAN NOTE:
A1 SEAL COAT WORK ON THE SHOULDERS AND SIDEROADS
SHALL BE DONE PRIOR TO MAINLINE MILLING OPERATIONS