

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	47RS-12	VERMILION	24	12

SCHEDULES OF QUANTITIES

SHEET 5 OF 5

78000100 THERMOPLASTIC PAVEMENT MARKING LTRS. & SYMB.

STATION	MRKNG TYPE	SO. FT.
2628+65.9	LT TURN ARROW	15.6
2629+70	LT TURN ARROW	15.6
TOTAL =		31.2
USE =		31.0

78000600 THERMOPLASTIC PAVEMENT MARKING-LINE 12" (YELLOW)

STATION	TO	STATION	LINE TYPE	LIN. FT.
RT 2629+91		RT 2629+94	DIAG	6.0
LT 2630+14		LT 2630+17	DIAG	6.0
2630+40		2630+41	DIAG	1.0
TOTAL =				13.0

78000200 THERMOPLASTIC PAVEMENT MARKING-LINE 4" (WHITE)

STATION	TO	STATION	LINE TYPE	LIN. FT.
RT 2627+92		RT 2662+21	SOLID	3429.0
LT 2628+55		LT 2665+08	SOLID	3653.0
LT 2628+65		LT 2629+70	SOLID	105.0
LT 2630+20		LT 2743+00	DASHED	3384.0
RT 2630+60		RT 2743+00	DASHED	3372.0
RT 2663+07		RT 2743+00	SOLID	7993.0
LT 2665+95		LT 2704+99	SOLID	3904.0
LT 2705+86		LT 2727+41	SOLID	2155.0
LT 2728+22		LT 2730+39	SOLID	217.0
LT 2731+06		LT 2743+00	SOLID	1194.0
TOTAL =				29406.0

78100100 RAISED REFLECTIVE MARKER (CRYSTAL MONODIRECTIONAL)

STATION	TO	STATION	EACH
2628+70		2629+70	3
LT 2630+45		LT 2742+05	139.5
RT 2630+45		RT 2742+05	139.5
SUB-TOTAL =			282.0

78100100 RAISED REFLECTIVE MARKERS (AMBER BIDIRECTIONAL)

STATION	TO	STATION	EACH
2628+70		2629+70	3
2629+70		2630+45	4
LT 2630+45		LT 2742+05	139.5
RT 2630+45		RT 2742+05	139.5
SUB-TOTAL =			286.0
TOTAL =			568.0

78000200 THERMOPLASTIC PAVEMENT MARKING-LINE 4" (YELLOW)

STATION	TO	STATION	LINE TYPE	LIN. FT.
RT 2628+65		RT 2629+70	DOUBLE SOLID	210.0
RT 2629+70		RT 2630+00	DOUBLE SOLID	60.0
RT 2629+70		RT 2630+45	DOUBLE SOLID	150.0
LT 2630+00		LT 2630+45	DOUBLE SOLID	90.0
2630+45		2743+10	DOUBLE SOLID	22530.0
TOTAL =				23040.0