

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55		McLEAN	87	4
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

90% FED.
10% STATE.

FUNDING: URBAN 90% FEDERAL, 10% STATE		CONSTRUCTION TYPE CODE:		I000	SFTY 2A			
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITY	STA. 36+305 TO STA. 40+486 ROADWAY	SN 057-0024 & SN 057-0025	SN 057-0026 & SN 057-0027	SN 057-0028 & SN 057-0029	SN 057-0214 & SN 057-0215
M2500600	POTASSIUM FERTILIZER NUTRIENT	KG	10.0	10.0				
M2510630	EROSION CONTROL BLANKET	SQ M	33.0	33.0				
M2810105	STONE RIPRAP, CLASS A3	SQ M	754.0	748.0			6.0	
M2810207	STONE RIPRAP, CLASS A4	M TON	8.1	8.1				
M2810707	STONE DUMPED RIPRAP, CLASS A4	SQ M	23.0					23.0
M2850100	FABRIC FORMED CONCRETE REVETMENT MAT	SQ M	360.0	360.0				
M4060100	BITUMINOUS MATERIALS (PRIME COAT)	LITER	23,637.0	23,637.0				
M4060400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	M TON	100.0	100.0				
M4060895	CONSTRUCTING TEST STRIP	EACH	2.0	2.0				
M4060990	TEMPORARY RAMP	SQ M	141.0	141.0				
M4063245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N105	M TON	3,389.0	3,389.0				
M4063575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N105	M TON	6,139.0	6,064.0			75.0	
M4080500	INCIDENTAL HOT-MIX ASPHALT SURFACING	M TON	50.0	50.0				
M4400735	HOT-MIX ASPHALT SURFACE REMOVAL, 35MM	SQ M	37,332.0	37,332.0				
M4400810	HOT-MIX ASPHALT SURFACE REMOVAL, 110MM	SQ M	13,128.0	13,128.0				
M4400950	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ M	844.0	844.0				
M4402115	HOT-MIX ASPHALT SURFACE REMOVAL, DECK	SQ M	815.0				815.0	
M4405000	PAVED DITCH REMOVAL	METER	108.0	108.0				
M4422350	PAVEMENT PATCHING, TYPE II 350MM	SQ M	471.0	471.0				
M4424350	PAVEMENT PATCHING, TYPE IV 350MM	SQ M	980.0	980.0				
M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	992.0	992.0				
M4820400	HOT-MIX ASPHALT SHOULDERS	M TON	1,112.0	1,112.0				
M5010240	CONCRETE REMOVAL	CU M	215.0		121.4	93.6		
M5010465	SLOPE WALL REMOVAL	SQ M	40.0		39.0		1.0	
M5010570	PROTECTIVE SHIELD	SQ M	1,068.0		604.0	464.0		
M5030360	CONCRETE SUPERSTRUCTURE	CU M	215.0		121.4	93.6		
M5030390	BRIDGE DECK GROOVING	SQ M	764.0		432.0	332.0		
M5030450	PROTECTIVE COAT	SQ M	943.0		537.0	406.0		
M5050405	FURNISHING AND ERECTING STRUCTURAL STEEL	KG	3,730.0			3,730.0		
M5080205	REINFORCEMENT BARS, EPOXY COATED	KG	29,820		16,950.0	12,870.0		
M5110100	SLOPE WALL 100 MM	SQ M	40.0		39.0		1.0	
M5200225	PREFORMED JOINT STRIP SEAL	METER	199.5		112.2	87.3		
M5810200	WATERPROOFING MEMBRANE SYSTEM	SQ M	815.0				815.0	
M6063400	PAVED DITCH, TYPE B-15	METER	26.0	26.0				

• SPECIALTY ITEMS
2 I000 100% STATE

SUMMARY OF QUANTITIES
F.A.I. 55
SECTION (57-4)RS-3 & I
MCLEAN COUNTY