

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	•	McLEAN	87	26
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

• (57-4)RS-3 & I

LOCATION	GUARDRAIL			
	GUARDRAIL MARKERS	TERMINAL MARKER - DIRECT APPLIED	STEEL PLATE BEAM GUARDRAIL TY. A	GUARDRAIL REMOVAL
	78200405	78201000	M6300100	M6320030
	EACH	EACH	METER	METER
STA. 37+049.591, RT.	1	---	---	---
STA. 37+319.668, RT. - STA. 37+413.550, RT.	4	---	---	---
STA. 37+334.868, RT. - STA. 37+399.634, RT.	---	---	64.77	---
STA. 37+336.333, RT. - STA. 37+416.571, RT.	---	---	---	80.45
STA. 37+349.727, RT.	1	---	---	---
STA. 37+434.315, RT.	1	---	---	---
STA. 37+502.545, LT.	1	---	---	---
STA. 37+530.648, LT. - STA. 37+610.976, LT.	---	---	---	80.52
STA. 37+535.148, LT. - STA. 37+628.269, LT.	4	---	---	---
STA. 37+548.302, LT. - STA. 37+613.069, LT.	---	---	64.77	---
STA. 37+581.934, LT.	1	---	---	---
STA. 38+033.271, RT.	1	---	---	---
STA. 38+117.680, RT. - STA. 38+211.563, RT.	4	---	---	---
STA. 38+132.880, RT. - STA. 38+197.647, RT.	---	---	64.77	---
STA. 38+135.134, RT. - STA. 38+215.295, RT.	---	---	---	80.39
STA. 38+195.797, RT. - STA. 38+210.801, RT.	1	---	15.0	15.0
STA. 38+231.728, RT.	1	---	---	---
STA. 38+235.837, LT.	1	---	---	---
STA. 38+310.742, LT. - STA. 38+391.317, LT.	---	---	---	80.80
STA. 38+314.382, LT. - STA. 38+408.265, LT.	4	---	---	---
STA. 38+328.298, LT. - STA. 38+393.065, LT.	---	---	64.77	---
STA. 38+400.879, RT. - STA. 38+525.242, RT.	5	---	---	---
STA. 38+416.079, RT. - STA. 38+511.326, RT.	---	---	95.25	---
STA. 38+480.769, RT. - STA. 38+529.951, RT.	---	---	---	50.06
STA. 38+513.505, RT. - STA. 38+517.318, RT.	---	---	---	3.81
STA. 38+517.318, RT.	1	---	---	---
STA. 38+557.150, LT. - STA. 38+606.303, LT.	---	---	---	49.97
STA. 38+559.241, LT.	1	---	---	---
STA. 38+562.089, LT. - STA. 38+686.452, LT.	5	---	---	---
STA. 38+569.344, LT. - STA. 38+573.157, LT.	---	---	---	3.81
STA. 38+576.005, LT. - STA. 38+671.252, LT.	---	---	95.25	---
STA. 38+633.431, LT.	1	---	---	---
STA. 40+155.956, RT.	1	---	---	---
STA. 40+330.874, LT.	1	---	---	---
⊙ EACH TRAFFIC BARRIER TY. 1 SPECIAL	---	13	---	---
TOTAL	40	13	464.58	444.81
USE			464.82	445

X0301894 - REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE DRAINS	
LOCATION	EACH
STA. 39+279.5, RT.	1
STA. 39+731.2, LT.	1
STA. 40+036.8, RT.	1
TOTAL	3

Z0030150 - IMPACT ATTENUATOR (NON-REDIRECTIVE) TEST LEVEL 3	
LOCATION	EACH
STA. 36+845, RT.	1
STA. 36+892, LT.	1
STA. 37+129, RT.	1
STA. 37+141, LT.	1
STA. 37+280, RT.	1
STA. 37+292, LT.	1
STA. 38+408, RT.	1
STA. 38+420, LT.	1
STA. 38+923, RT.	1
STA. 38+935, LT.	1
STA. 39+409, RT.	1
STA. 39+421, LT.	1
STA. 40+238, TL.	1
STA. 40+264, TL.	1
TOTAL	14

Z0030350 - IMPACT ATTENUATOR, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	
LOCATION	EACH
STA. 37+330, RT	1
STA. 38+439, LT	1
TOTAL	2

TEMPORARY PAVEMENT MARKING, 100 MM	
LOCATION	M7030220 METER
STAGE 1 WHITE	
STA. 36+305.0 - STA. 36+640.0 NB, OUTSIDE EDGE	335.0
STA. 36+640.0 - STA. 37+350.0 NB, SKIP DASH BETWEEN LANES	71.0
STA. 37+350.0 - STA. 37+509.5 NB, OUTSIDE EDGE	159.5
STA. 37+350.0 - STA. 38+044.0 NB, BETWEEN LANES	694.0
STA. 38+287.6 - STA. 38+625.0 NB, OUTSIDE EDGE	337.4
STA. 38+625.0 - STA. 40+486.0 NB, OUTSIDE EDGE	1861.0
STA. 36+305.0 - STA. 36+625.0 SB, OUTSIDE EDGE	320.0
STA. 38+426.9 - STA. 38+700.0 SB, OUTSIDE EDGE	273.1
STA. 38+700.0 - STA. 40+486.0 SB, OUTSIDE EDGE	1786.0
STAGE 2 YELLOW	
STA. 36+305.0 - STA. 37+350.0 NB, INSIDE EDGE	1045.0
STA. 37+350.0 - STA. 38+575.0 NB, INSIDE EDGE	1225.0
STA. 38+575.0 - STA. 40+486.0 NB, INSIDE EDGE	1911.0
STA. 37+915.6 - STA. 38+125.0 RAMP D LEFT EDGE	209.4
STA. 36+305.0 - STA. 38+100.0 SB, INSIDE EDGE	1795.0
STA. 38+100.0 - STA. 38+625.0 SB, INSIDE EDGE	525.0
STA. 38+625.0 - STA. 40+486.0 SB, INSIDE EDGE	1861.0
STAGE 2 WHITE	
STA. 36+305.0 - STA. 38+100.0 SB, OUTSIDE EDGE	320.0
STA. 36+305.0 - STA. 38+100.0 SB, OUTSIDE EDGE	1230.0
TOTAL WHITE	7387.0
TOTAL YELLOW	8571.4
TOTAL	15958.4
USE	15959

POLYURETHANE MATERIAL	
LOCATION	CU M
STA. 38+300, RT. (EAST BRIDGE APPROACH PAVEMENT DRIVING LANE SN 057-0026)	3
TOTAL	3

Z0030250 - IMPACT ATTENUATOR, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3		
LOCATION	STAGE 1 EACH	STAGE 2 EACH
STA. 37+377, RT	1	
STA. 37+522, LT		1
STA. 38+623, LT	1	
TOTAL		3

PAVEMENT MARKING				
LOCATION	POLYUREA PAVEMENT MARKING, TYPE II			
	LINE 100 MM	LINE 100 MM	LINE 200 MM	LINE 300 MM
	METER	METER	METER	METER
STA. 36+305.000, LT.- STA. 36+630.100, LT.	325.1			
STA. 36+305.000, RT.- STA. 36+485.000, RT.	180.0			
STA. 36+305.000, LT. - STA. 40+486.000, LT.		4181		
STA. 36+305.000, RT. - STA. 40+486.000, RT.		4181		
STA. 36+485.000, RT. - STA. 36+650.210, RT.			165.2	
STA. 36+864.880, LT. - STA. 38+332.800, LT.	1467.9			
STA. 36+924.990, LT. - STA. 37+249.000, LT.				177.3
STA. 37+293.990, LT. - STA. 38+104.000, LT.				113.8
STA. 37+412.790, RT. - STA. 37+658.220, RT.			245.4	
STA. 37+541.000, RT. - STA. 37+649.000, RT.				100.0
STA. 37+658.220, RT. - STA. 37+950.820, RT.	292.6			
STA. 37+950.820, RT. - STA. 38+086.890, RT.			136.1	
STA. 38+124.990, LT. - STA. 38+280.990, LT.				95.6
STA. 38+358.500, RT. - STA. 40+486.000 RT.	2127.5			
STA. 38+424.580, LT. - STA. 40+486.000, LT.	2061.4			
TOTAL	6454.5	8362	546.7	486.7
USE			547	487