

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57&74	*	**	151	16

\* D5 CABLE GUARD 2007-2  
 \*\* CHAMPAIGN, DEWITT & DOUGLAS

## SCHEDULES OF QUANTITIES

### EARTHWORK ANALYSIS

LOCATION	20200100 EARTH EXCAVATION ( CU. YD. )	EARTH EX. SHRINK( 25% ) ( CU. YD. )	EMBANKMENT ( CU. YD. )	20400800 FURNISHED EXCAVATION ( CU. YD. )
<u>DOUGLAS COUNTY</u>				
LOC #1 TUSCOLA ( I-57 SBDL SHOULDER ) LT. STA. 466+50 - 504+00	442.0	331.5	678.7	348.0
<u>CHAMPAIGN COUNTY</u>				
LOC #2 PESOTUM ( I-57 SBPL MEDIAN ) LT. STA. 173+50 - 251+00	2245.0	1684.0	4055.0	2371.0
<u>DEWITT COUNTY</u>				
LOC #3 FARMER CITY ( I-74 EBPL MEDIAN ) RT. STA. 711+50 - 744+50	221.0 <del>172.0</del>	165.8 <del>129.0</del>	2067.6 <del>1451.7</del>	1902.0 <del>1323.0</del>
TOTALS =	2908.0 <del>2859.0</del>			4621.0 <del>4042.0</del>



### SEEDING SUMMARY

LOCATION	25000200 SEEDING CLASS 2 ( ACRE )	25000400 NITROGEN ( POUND )	25000500 PHOSPHORUS ( POUND )	25000600 POTASSIUM ( POUND )	25100115 MULCH METHOD 2 ( ACRE )	28000250 TEMP. EROS. CTL SEEDING ( POUND )
<u>DOUGLAS COUNTY</u>						
LOC #1 TUSCOLA ( I-57 SBDL SHOULDER ) LT. STA. 466+50 - 504+00	2.1	189.0	189.0	189.0	2.1	210.0
<u>CHAMPAIGN COUNTY</u>						
LOC #2 PESOTUM ( I-57 SBPL MEDIAN ) LT. STA. 173+50 - 251+00	7.0	630.0	630.0	630.0	7.0	700.0
<u>DEWITT COUNTY</u>						
LOC #3 FARMER CITY ( I-74 EBPL MEDIAN ) RT. STA. 711+50 - 744+50	2.4	216.0	216.0	216.0	2.4	240.0
TOTALS =	11.5	1035.0	1035.0	1035.0	11.5	1150.0

PLOT DATE = 4/1/2007  
 PLOT SCALE = 1" = 500'  
 USER NAME = philip

△ REVISED 4/10/07