

F.A.P. RTE. ①	SECTION ②	COUNTY	TOTAL SHEETS	SHEET NO.
		SANGAMON	80	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

① FAP 666 & FAP 67
 ② (SP-2)RS-4; (107)RS-8

CODED PAY ITEM	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODE					
				ROADWAY NINTH ST	ROADWAY JEFFERSON ST	TRAFFIC SIGNALS NINTH ST - SEE NOTE 1	TRAFFIC SIGNALS NINTH ST - SEE NOTE 2	PARKING JEFFERSON ST	ADJUSTMENTS JEFFERSON ST
				80% FEDERAL	80% FEDERAL	80% FEDERAL	80% FEDERAL	50% STATE	100% CITY
				20% STATE	20% STATE	20% STATE	10% STATE / 10% CITY	50% CITY	
URBAN SANGAMON CO. 1000	URBAN SANGAMON CO. 1000	URBAN SANGAMON CO. Y031-1F	URBAN SANGAMON CO. Y031-1F	URBAN SANGAMON CO. Y025	URBAN SANGAMON CO. Y060				
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	118			111	7		
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4			3	1		
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1			1			
86300400	CONTROLLER CABINET TYPE IV	EACH	1				1		
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1			1			
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	487.0			487.0			
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14, 5C	FOOT	1160.0			1160.0			
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14, 7C	FOOT	1393.5			1056.5	337.0		
87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14, 9C	FOOT	524.0			524.0			
87301275	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14, 12C	FOOT	444.5			444.5			
87301525	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 18, 6 PAIR	FOOT	1437.5			686.0	751.5		
87301815	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 3C	FOOT	32.0			32.0			
87502290	TRAFFIC SIGNAL POST, PAINTED STEEL 14 FT.	EACH	1			1			
87502310	TRAFFIC SIGNAL POST, PAINTED STEEL 16 FT.	EACH	1				1		
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	1			1			
87600200	PEDESTRIAN PUSH-BUTTON POST, TYPE II	EACH	1				1		
87700140	STEEL MAST ARM ASSEMBLY AND POLE, 20 FT.	EACH	1			1			
87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	1			1			
87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	1			1			
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1			1			
87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	2				2		
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	2			2			
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1			1			
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6			6			
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3			3			
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	87.5			60.5	27.0		
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	13.0			13.0			
87900200	DRILL EXISTING HANDHOLE	EACH	7			6	1		
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	10			8	2		
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	30			17	13		

NOTE 1: NINTH ST WITH INTERSECTIONS OF: MADISON, JEFFERSON, AND SOUTH GRAND
 NOTE 2: NINTH ST WITH INTERSECTIONS OF: CONVERSE, ENOS, CARPENTER, WASHINGTON, AND COOK

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAP 666 (I-55 BUSINESS LOOP-NINTH STREET)
 FAP 67 (IL 97/IL 29-JEFFERSON STREET)
 SCALE: VERT. _____
 DATE _____
 DRAWN BY _____
 CHECKED BY _____

PLT DATE : 00/00/00
 FILE NAME : 000000
 PLOT SCALE : 000000
 USER NAME : 000000