

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
①	②	SANGAMON	80	14
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
① FAP 666 & FAP 67				
② (SP-2)RS-4 & (107)RS-8				

SIDE STREET PAVING

LOCATION	SIDE	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	INCIDENTAL HOT-MIX ASPHALT SURFACING	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE MIX D N70
		SO YD	SO YD	TON	TON	TON	TON
NINTH STREET							
NORTH GRAND	LT	195	20	0.08	0.20	22	
NORTH GRAND	RT	125	20	0.05	0.13	14	
RESERVOIR	LT	43	9	0.02	0.04	5	
DIVISION	LT	50	10	0.02	0.05	6	
DIVISION	RT	49	10	0.02	0.05	5	
ENTERPRISE	LT	53	10	0.02	0.05	6	
ENTERPRISE	RT	48	10	0.02	0.05	5	
PHILLIPS	LT	34	8	0.01	0.03	4	
PHILLIPS	RT	42	8	0.02	0.04	5	
ENOS	LT	45	10	0.02	0.05	5	
ENOS	RT	47	10	0.02	0.05	5	
MILLER	LT	56	9	0.02	0.06	6	
MILLER	RT	27	10	0.01	0.03	3	
CARPENTER	LT	90	14	0.04	0.09		8
CARPENTER	RT	78	13	0.03	0.08		7
REYNOLDS	LT	50	9	0.02	0.05	6	
MASON	LT	41	10	0.02	0.04	5	
ENTRANCE (STA 2+49.35)	RT	112	13	0.04	0.11	13	
WASHINGTON	LT	71	19	0.03	0.07	8	
WASHINGTON	RT	119	18	0.05	0.12	13	
ADAMS	LT	97	16	0.04	0.10	11	
ADAMS	RT	91	16	0.04	0.09	10	
MONROE	LT	108	15	0.04	0.11	12	
MONROE	RT	99	16	0.04	0.10	11	
CAPITOL	LT	107	15	0.04	0.11	12	
CAPITOL	RT	112	15	0.04	0.11	13	
JACKSON	LT	32	12	0.01	0.03	4	
EDWARDS	LT	70	10	0.03	0.07	8	
EDWARDS	RT	61	10	0.02	0.06	7	
COOK	LT	267	27	0.11	0.27		23
COOK	RT	96	14	0.04	0.10		8
LAWRENCE	LT	49	10	0.02	0.05	5	
LAWRENCE	RT	84	13	0.03	0.08	9	
CASS	LT	61	10	0.02	0.06	7	
CASS	RT	62	10	0.02	0.06	7	
CLAY	RT	76	12	0.03	0.08	9	
SCARRITT	RT	63	12	0.02	0.06	7	
ALLEN	RT	87	12	0.04	0.09	10	
VINE	RT	78	12	0.03	0.08	9	
SOUTH GRAND	LT	19		0.01	0.02		2
SOUTH GRAND	RT	36		0.02	0.04		3
SUBTOTAL		3130	497	1.3	3	287	51
JEFFERSON STREET							
1ST STREET	LT	188	16	0.08		16	
1ST STREET	RT	79	16	0.03		7	
2ND STREET	LT	96	16	0.04		8	
2ND STREET	RT	82	16	0.03		7	
4TH STREET	LT	79	13	0.03		7	
4TH STREET	RT	77	13	0.03		6	
5TH STREET	LT	92	16	0.04			8
5TH STREET	RT	103	17	0.04			9
6TH STREET	LT	95	16	0.04			8
6TH STREET	RT	104	16	0.04			9
7TH STREET	LT	96	16	0.04		8	
7TH STREET	RT	95	16	0.04		8	
9TH STREET	LT	107	20	0.04		9	
9TH STREET	RT	114	20	0.04		10	
11TH STREET	LT	100	17	0.04		8	
11TH STREET	RT	49	17	0.02		4	
SUBTOTAL		1556	261	0.6		98	34
PROJECT TOTAL		4686	758	1.9	3	385	85

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

FAP 666 (I-55 BUSINESS LOOP-NINTH STREET)

FAP 67 (IL 97/IL 29-JEFFERSON STREET)

SCALE: VERT. / HORIZ.

DATE: / /

DRAWN BY: / /

CHECKED BY: / /

PLOT DATE = 2/15/2007
 FILE NAME = c:\projects\6565803\hls\lma\schedulao\quantities.dgn
 PLOT SCALE = 4.2352" / IN.
 USER NAME = laughlin-1

\$\$\$