

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
67	S(RS-5, TS-7), L	SANGAMON	78	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

	HSIP			
ROADWAY	INTERSECTION OF JEFFERSON ST. AND VETERANS PKWY	INTERSECTION OF JEFFERSON ST. AND CHURCHILL DR.	STREET LIGHTING STA. 126+50 TO STA. 143+00	SIDEWALK
80% FEDERAL 20% STATE	90% FEDERAL 10% STATE	90% FEDERAL 5% STATE 5% CITY	90% FEDERAL 10% STATE	50% STATE 50% CITY

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE				
				1000	Y031-1F	Y031-1F	Y030-1E	SFTY-1B
20200100	EARTH EXCAVATION	CU YD	500					500
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	39					39
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	2.5					2.5
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	15.5					15.5
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.1					0.1
25200110	SODDING, SALT TOLERANT	SO YD	2100					2100
25200200	SUPPLEMENTAL WATERING	UNIT	19					19
31200100	STABILIZED SUB-BASE 4"	SO YD	132	132				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7.5	7.5				
40600300	AGGREGATE (PRIME COAT)	TON	36	36				
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	969	969				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	272	272				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	1324	1324				
40600990	TEMPORARY RAMP	SO YD	212	212				
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1492	1492				
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	27	27				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SO YD	108					108
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	7576					7576
42400800	DETECTABLE WARNINGS	SO FT	60					60
44000157	HOT-MIX ASPHALT SURFACE REMOVAL 2"	SO YD	1265.5	1265.5				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	108					108
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	11	11				
44003100	MEDIAN REMOVAL	SO FT	1121	1121				
44003900	MEDIAN SURFACE REMOVAL & REPLACEMENT	SO FT	92	92				
44200553	CLASS A PATCHES, TYPE II, 10 INCH	SO YD	1191	1191				
44200557	CLASS A PATCHES, TYPE III, 10 INCH	SO YD	64	64				
44200559	CLASS A PATCHES, TYPE IV, 10 INCH	SO YD	25	25				
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	400	400				

Handwritten corrections in a cloud shape:
 1191 1191
 64 64
 25 25
 400 400
 A

PLT DATE : MONTH
 PLT SCALE : SCALE
 REFERENCE : REF

Rev. 4-5-07

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAP 67 (IL 97/ JEFFERSON ST)
 SECTION S(RS-5, TS-7), L
 SANGAMON COUNTY
 SCALE: VERT. _____
 DATE _____ HORIZ. _____
 DRAWN BY _____
 CHECKED BY _____