

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
714	(135)RS-6, TS	CHRISTIAN	47	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES				<i>F</i> 80% FED. / 20% STATE		<i>HSIP</i> 90% FED. / 10% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	RURAL ROADWAY SEE NOTE 1	URBAN ROADWAY SEE NOTE 2	URBAN TRAFFIC SIGNALS	
				1000-2A	1000-2A	Y031-1F	
20400800	FURNISHED EXCAVATION	CU YD	140		140		
35800100	PREPARATION OF BASE	SQ YD	180	18.7	161.3		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	36	2.9	33.1		
40600300	AGGREGATE (PRIME COAT)	TON	174	14.4	159.6		
40600895	CONSTRUCTING TEST STRIP	EACH	1		1		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1029	81.6	947.4		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	247		247		
40600990	TEMPORARY RAMP	SQ YD	157	13.6	143.4		
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7362	604.8	6757.2		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	88	6.1	81.9		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	18327.5		18327.5		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	933		933		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	68517	7146.7	61370.3		
44200152	PAVEMENT PATCHING, TYPE I, 13 INCH	SQ YD	100	50	50		
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	788	68	720		
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	224	16	208		
44200162	PAVEMENT PATCHING, TYPE IV, 13 INCH	SQ YD	83		83		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2408	258.3	2149.7		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	105		105		
50300225	CONCRETE STRUCTURES	CU YD	11.6		11.6		
50800205	REINFORCEMENT BARS, EXPOXY COATED	POUND	1430		1430		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	750		750		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	8		8		
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	8		8		
63200305	STEEL PLATE BEAM GUARD RAIL REMOVAL	FOOT	690	312	378		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	0.5	3	0.5	
67100100	MOBILIZATION	L SUM	1	0.2	0.6	0.2	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.2	0.6	0.2	

- NOTES:
1. STA. 0+00 TO STA. 26+80
 2. STA. 26+80 TO STA. 68+12.31
 STA. EQ. 68+12.31BK=23+53.94AH
 STA. 23+53.94 TO STA. 112+99.14
 STA. EQ. 112+99.14BK=112+97.33AH
 STA. 112+97.33 TO STA. 188+05.74
 STA. EQ. 188+05.74BK=188+02.67AH
 STA. 188+02.67 TO STA. 227+41.20
 STA. EQ. 227+41.20BK=64+00AH
 STA. 64+00 TO STA. 64+20

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAP ROUTE 714 (IL 48)
 SECTION (135)RS-6, TS
 CHRISTIAN COUNTY

SCALE: VERT. _____
 HORIZ. _____

DATE _____ DRAWN BY _____
 CHECKED BY _____

PLT DATE : 08/15/04
 FILE NAME : 081504.DWG
 PLOT SCALE : 1"=40'
 USER NAME : MUSER