

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
714	(135)RS-6,TS	CHRISTIAN	47	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PAVEMENT SCHEDULE

LOCATION STATION TO STATION	LENGTH (FT)	WIDTH (FT)	AVERAGE WIDTH (FT)	BIT SURF THICKNESS (IN)	HOT-MIX ASPHALT SURF REMOV BUTT-JOINT (SQ YD)	HOT-MIX ASPHALT SURF REMOV (VAR DEPTH) (SQ YD)	HOT-MIX ASPHALT SURF REMOV (1 1/2") (SQ YD)	HOT-MIX ASPHALT SURF CSE MIX "D" N70 (TON)	BIT MAT PRIME CT (TON)	AGG PRIME CT (TON)	
FAP 714 (ILL RTE 48)											
STA -0+20 TO STA 35+50.00	3,570.00	24.00	24.00	1.5	53.2	9466.7	-	799.7	3.6	19.0	
STA 35+50.00 TO STA. 37+67.98	217.98	VARIES 24.00 TO 30.16	27.08	1.5	-	655.9	-	55.1	0.2	1.3	
STA. 37+67.98 LT. TO STA. 50+59.00 LT.	1,291.02	16.00	16.00	1.5	-	-	2362.9	198.5	0.9	4.7	
STA. 37+67.98 RT. TO STA. 50+59.00 RT.	1,291.02	VARIES 14.00 TO 28.00	21.00	1.5	-	-	2888.7	242.7	1.1	5.8	
STA. 50+59.00 TO STA 52+84.90	225.90	VARIES 34.00 TO 24.00	29.00	1.5	-	-	728.0	61.2	0.3	1.5	
STA 52+84.90 TO STA 68+12.31	1,527.41	24.00	24.00	1.5	-	3062.7	1010.4	342.1	1.5	8.1	
STA. EQ. 68+12.31 BK. = 23+53.94 AH.											
STA 23+53.94 TO STA 72+91.40	4,937.46	24.00	24.00	1.5	-	13166.6	-	1106.0	5.0	26.3	
STA 72+91.40 TO STA 73+86.00	94.60	VARIES 24.00 TO 31.50	27.75	1.5	-	291.7	-	24.5	0.1	0.6	
STA. 73+86.00 LT. TO STA. 87+51.00 LT.	1,365.00	VARIES 14.00 TO 36.00	25.00	1.5	-	-	3048.8	256.1	1.2	6.1	
STA. 73+86.00 RT. TO STA. 87+51.00 RT.	1,365.00	VARIES 14.00 TO 40.00	27.00	1.5	-	-	3400.3	285.6	1.3	6.8	
STA. 87+51.00 TO STA. 91+30.00	379.00	VARIES 31.50 TO 24.00	27.75	1.5	-	1168.6	-	98.2	0.4	2.3	
STA 91+30.00 TO STA 112+99.14	2,169.14	24.00	24.00	1.5	-	5784.4	-	485.9	2.2	11.6	
STA. EQ. 112+99.14 BK. = 112+97.33 AH.											
STA 112+97.33 TO STA 180+73.00	6,775.67	24.00	24.00	1.5	-	17668.5	400	1517.8	6.7	35.3	
STA 180+73.00 TO STA 188+05.74	732.74	VARIES 24.00 TO 34.00	29.00	1.5	-	1822.0	1162.2	250.7	1.1	6.0	
STA. EQ. 188+05.74 BK. = 188+02.64 AH.											
STA 188+02.64 TO STA 196+70.00	867.36	VARIES 24.00 TO 34.00	29.00	1.5	-	2426.9	1028.9	290.3	1.3	6.9	
STA 196+70.00 TO STA 208+79.00	1,209.00	24.00	24.00	1.5	-	3224.0	-	270.8	1.2	6.4	
STA 208+79.00 TO STA 217+98.00	919.00	VARIES 24.00 TO 38.00	31.00	1.5	-	3106.1	-	260.9	1.2	6.2	
STA 217+98.00 TO STA 227+41.20	943.20	24.00	24.00	1.5	-	2514.7	-	211.2	1.0	5.0	
STA. EQ. 227+41.20 BK. = 64+00.00 AH.											
STA 64+00.00 TO STA 64+20.00	20.00	24.00	24.00	1.5	48.8	-	-	4.1	0.1	0.1	
					TOTALS	102.0	64359.0	16030.3	6761.6	30.5	160.3

PLOT DATE = #DATE#
 FILE NAME = #FILE#
 PLOT SCALE = #SCALE#
 USER NAME = #USER#

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
FA ROUTE 714 (IL 48)
SECTION (135)RS-6,TS
CHRISTIAN COUNTY

SCALE: VERT. _____
 HORIZ. _____

DATE _____ DRAWN BY _____
 CHECKED BY _____