

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
714	(135)RS-6,TS	CHRISTIAN	47	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SIDE ROAD, ENTRANCE AND MAILBOX TURNOUT SCHEDULE													
LOCATION	EXIST SURF TYPE	WIDTH ACROSS FRONT (FT)	WIDTH ACROSS BACK (FT)	LENGTH (FROM EDGE OF PVT, TO LIMITS OF IMPROVEMENT) (FOOT)	PERPARATION OF BASE (SQ YD)	HOT-MIX ASPHALT SURF REMOV BUTT-JOINT (SQ YD)	PCC SURF REMOVAL BUTT-JOINT (SQ YD)	HOT-MIX ASPHALT SURF REMOVAL (VAR DEPTH) (SQ YD)	HOT-MIX ASPHALT REMOVAL (1 1/2") (SQ YD)	INCIDENTAL HOT-MIX SURFACING (TON)	HOT-MIX ASPHALT SURF CSE MIX "D" N70 (TON)	BIT MAT PRIME CT (TON)	AGG PRIME CT (TON)
P. E. LT. STA. 0+43	BIT.	40	24	8	-	28.4	-	-	-	2.4	-	0.1	-
F. E. RT. STA. 1+58	AGG.	40.00	24	-	-	-	-	-	-	-	-	-	-
P. E. LT. STA. 4+25	AGG.	30	12	8	18.7	-	-	-	-	3.7	-	0.1	-
F. E. RT. STA. 11+02	EARTH	45	12	-	-	-	-	-	-	-	-	-	-
F. E. LT. STA. 19+00	EARTH	10	10	-	-	-	-	-	-	-	-	-	-
F. E. RT. STA. 19+00	EARTH	12	12	-	-	-	-	-	-	-	-	-	-
P. E. RT. STA. 27+70	BIT.	30	10	8	-	17.8	-	-	-	1.5	-	0.1	-
F. E. LT. STA. 29+83.50	AGG.	59	12	-	-	-	-	-	-	-	-	-	-
F. E. RT. STA. 35+00	EARTH	16.5	16.5	-	-	-	-	-	-	-	-	-	-
F. E. LT. STA. 35+04	AGG.	22.5	22.5	-	-	-	-	-	-	-	-	-	-
SPRESSER ST. LT. STA. 45+02.20	BIT.	166	25	92	-	57.8	-	435.3	-	-	41.4	0.2	1.0
SPRESSER ST. RT. STA. 45+02.20	BIT.	108	20	27	-	-	-	-	113.6	-	9.5	0.1	0.2
P. E. LT. STA. 66+16	AGG.	35	17	8	23.1	-	-	-	-	4.5	-	0.1	-
F. E. RT. STA. 66+23	EARTH	21	16	-	-	-	-	-	-	-	-	-	-
STA. EO. 68+12.31 BK. = 23+53.94 AH.													
C. E. LT. STA. 38+00	AGG.	40	16	10	31.1	-	-	-	-	13.9	-	0.1	-
F. E. RT. STA. 38+00	EARTH	16	12	-	-	-	-	-	-	-	-	-	-
F. E. RT. STA. 40+25	EARTH	19	19	-	-	-	-	-	-	-	-	-	-
HOUSTON ST. LT. STA. 40+80	BIT.	105	55	15	-	133.3	-	-	-	11.2	-	0.1	-
P. E. RT. STA. 41+11	OIL & CHIP	30	12	8	-	18.7	-	-	-	1.6	-	0.1	-
P. E. RT. STA. 48+58	BIT.	35	17	8	-	23.1	-	-	-	1.9	-	0.1	-
P. E. RT. STA. 61+18.5	BIT.	35	16	8	-	22.7	-	-	-	1.9	-	0.1	-
P. E. RT. STA. 61+68.5	CONC.	45	20	8	-	-	28.9	-	-	2.4	-	0.1	-
M. B. LT. STA. 61+68.5	BIT.	66	22	8	-	39.1	-	-	-	3.3	-	0.1	-
P. E. LT. W/ M. B. STA. 66+50.5	BIT.	72	39	8	-	49.3	-	-	-	4.1	-	0.1	-
NOKOMIS RD. LT. STA. 80+80.82	BIT.	307	SEE SHEET 34 FOR DIMENSION	-	-	93.3	-	1019.6	-	-	93.5	0.4	2.2
NOKOMIS RD. RT. STA. 80+80.82	BIT.	191	SEE SHEET 34 FOR DIMENSION	-	-	86.6	-	1253.7	-	-	112.6	0.5	2.7
STA. EO. 112+99.14 BK. = 112+97.33 AH.													
CHEROKEE ST. LT. STA. 116+15	CONC.	112	30	-	-	-	199.2	-	-	-	20.9	0.1	-
TR. 1300 E. RT. STA. 116+15	BIT.	103	55	15	-	131.7	-	-	-	11.1	-	0.1	-
P. E. LT. STA. 148+11	AGG.	40	23	8	28.0	-	-	-	-	5.5	-	0.1	-
P. E. & F. E. RT. ST. 151+58	CONC.	30	12	8	-	-	18.7	-	-	1.6	-	0.1	-
F. E. LT. STA. 155+26	EARTH	13	13	-	-	-	-	-	-	-	-	-	-
P. E. RT. STA. 155+41	AGG.	97	81	8	79.1	-	-	-	-	15.5	-	0.1	-
BIKE PATH LT. STA. 168+78	BIT.	11	11	8	-	9.8	-	-	-	0.8	-	0.1	-
BIKE PATH RT. STA. 168+78	BIT.	11	11	8	-	9.8	-	-	-	0.8	-	0.1	-
F. E. LT. STA. 171+48.50	EARTH	12	12	-	-	-	-	-	-	-	-	-	-
STA. EO. 227+41.20 BK. = 64+00.00 AH.													
E. MAIN CROSS ST. LT. STA. 188+12.23	BIT.	325	SEE SHEET 37 FOR DIMENSION	-	-	71.1	-	-	1101.1	-	98.5	0.4	2.3
LINCOLN TRAIL RD. RT. STA. 188+12.23	BIT.	325	SEE SHEET 37 FOR DIMENSION	-	-	71.1	-	-	1082.6	-	96.9	0.4	2.3
F. E. RT. STA. 210+96.50	AGG.	14	14	-	-	-	-	-	-	-	-	-	-
MCADAM DR. LT. STA. 211+73.30	BIT.	230	SEE SHEET 39 FOR DIMENSION	-	-	63.4	-	1449.7	-	-	127.1	0.6	3.0
					180.0	927.0	247.0	4158.0	2297.2	88.0	600.4	4.5	13.7

PLOT DATE = \$DATE\$  
 FILE NAME = \$FILEL\$  
 PLOT SCALE = \$SCALE\$  
 USER NAME = \$USER\$

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULE OF QUANTITIES**  
**FA ROUTE 714 (IL 48)**  
**SECTION (135)RS-6,TS**  
**CHRISTIAN COUNTY**

SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_

DATE \_\_\_\_\_ DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_