

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
714	(135)RS-6,TS	CHRISTIAN	47	12
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

RAISED REFLECTIVE PAVEMENT MARKERS SCHEDULE

STATION	TO	STATION	LENGTH (FT)	SPACING	TWO-WAY AMBER (EACH)	ONE-WAY AMBER (EACH)	ONE-WAY CRYSTAL (EACH)
STA. 0+00.0	TO	STA. 34+30.0	3430.0	1 @ 80'	43		
STA. 34+30.0	TO	STA. 54+05.0	3842.0	1 @ 40'		41	
STA. 42+54.0	TO	STA. 44+82.0	228.0	1 @ 40'			6
STA. 54+05.0	TO	STA. 68+12.0	1407.0	1 @ 80'	18		
STA. 68+12.0 BK	TO	STA. 23+54.0 AH					
STA. 23+54.0	TO	STA. 71+71.0	4817.0	1 @ 80'	61		
STA. 71+71.0	TO	STA. 91+20.0	3570.0	1 @ 40'		42	
STA. 77+78.0	TO	STA. 80+47.0	441.0	1 @ 40'			11
STA. 81+14.0	TO	STA. 83+85.0	435.0	1 @ 40'			11
STA. 91+20.0	TO	STA. 112+99.0	2179.0	1 @ 80'	28		
STA. 112+99.0 BK	TO	STA. 112+97.0 AH					
STA. 112+97.0	TO	STA. 179+74.0	6677.0	1 @ 80'	84		
STA. 179+74.0	TO	STA. 188+06.0	1576.0	1 @ 40'		40	
STA. 185+94.0	TO	STA. 187+62.0	168.0	1 @ 40'			5
STA. 188+06.0 BK	TO	STA. 188+03.0 AH					
STA. 188+62.0 BK	TO	STA. 190+26.0 AH	164.0	1 @ 40'			5
STA. 188+03.0	TO	STA. 196+38.0	1552.0	1 @ 40'		40	
STA. 196+38.0	TO	STA. 227+41.0	3103.0	1 @ 80'	40		
STA. 227+41.0 BK	TO	STA. 64+00.0 AH					
STA. 64+00.0	TO	STA. 64+35.0	35.0	1 @ 80'	1		
SUB-TOTAL					275	163	38
TOTAL						476	

RAISED REFLECTIVE PAVEMENT MARKERS REMOVAL

STATION TO STATION	QUANTITY (EACH)	
STA. 0+00.0 TO STA. 35+50.0	45	
STA. 35+50.0 TO STA. 52+85.0	14	
STA. 52+85.0 TO STA. 68+12.0	19	
STA. EQ. 68+12 BK = 23+54 AH		
STA. 23+54.0 TO STA. 72+91.0	62	
STA. 72+91.0 TO STA. 90+00.0	38	
STA. 90+00.0 TO STA. 112+99.0	29	
STA. EQ. 112+99 BK = 112+97 AH		
STA. 112+97.0 TO STA. 180+94.0	85	
STA. 180+94.0 TO STA. 188+06.0	25	
STA. EQ. 188+06 BK = 188+03 AH		
STA. 188+03.0 TO STA. 195+18.0	27	
STA. 195+18.0 TO STA. 227+41.0	41	
STA. EQ. 227+41 BK = 64+00 AH		
STA. 64+00.0 TO STA. 64+35.0	1	
TOTAL		386

SHORT-TERM PAVEMENT MARKING & WORK ZONE PAVEMENT MAKING REMOVAL SCHEDULE

STATION TO STATION	LOCATION	DESCRIPTION	LENGTH (FT)	QUANTITY		
				SHORT-TERM MARK	PAVT	WORK ZONE PAVT MR
				WHITE (FT)	YELLOW (FT)	(SQ FT)
IL48						
STA. 0+00.0	TO	STA. 35+50.0	CENTER LINE	SKIP-DASH	3550.0	710 118.2
STA. 35+50.0	TO	STA. 37+69.0	CENTER LINE	DOUBLE SKIP-DASH	438	87.6 14.6
STA. 42+54.0	TO	STA. 44+82.0	CENTER LINE	SKIP-DASH	228.0 45.6	7.6
STA. 50+59.0	TO	STA. 52+85.0	CENTER LINE	DOUBLE SKIP-DASH	452	90.4 15.1
STA. 52+85.0	TO	STA. 68+12.3	CENTER LINE	SKIP-DASH	1527.3	305.46 50.9
STATION EQUATION STA. 68+12.3 BK TO STA. 23+53.9 AH						
STA. 23+53.9	TO	STA. 72+91.0	CENTER LINE	SKIP-DASH	4937.1	987.412 164.4
STA. 72+91.0	TO	STA. 73+88.0	CENTER LINE	SKIP-DASH	194.0	38.8 6.5
STA. 77+78.0	TO	STA. 80+47.0	LANE LINE (RT)	SKIP-DASH	431.0 86.2	14.4
STA. 80+14.0	TO	STA. 83+85.0	LANE LINE (LT)	SKIP-DASH	435 87	14.5
STA. 87+50.0	TO	STA. 90+00.0	CENTER LINE	DOUBLE SKIP-DASH	500	100 16.7
STA. 90+00.0	TO	STA. 112+99.0	CENTER LINE	SKIP-DASH	2299	459.8 76.6
STATION EQUATION STA. 112+99 BK TO STA. 112+97.3 AH						
STA. 112+97.3	TO	STA. 180+94.0	CENTER LINE	SKIP-DASH	6797	1359.4 226.3
STA. 180+94.0	TO	STA. 185+94.0	CENTER LINE	DOUBLE SKIP-DASH	1000.0	200 33.0
STA. 185+94.0	TO	STA. 187+62.0	CENTER LINE AND LANE LINE	SKIP-DASH	336 33.6	33.6 11.2
STATION EQUATION STA. 188+05.7 BK TO STA. 188+02.7 AH						
STA. 188+62.0	TO	STA. 190+26.0	CENTER LINE AND LANE LINE	SKIP-DASH	328 32.8	32.8 10.9
STA. 190+26.0	TO	STA. 195+18.0	CENTER LINE	DOUBLE SKIP-DASH	984	196.8 32.8
STA. 195+18.0	TO	STA. 227+41.0	CENTER LINE	SKIP-DASH	3223	644.6 107.3
STA. 211+19.0	TO	STA. 215+11.0	LANE LINE	SKIP-DASH	392 78.4	13.1
STATION EQUATION STA. 227+41.0 BK TO STA. 64+00.0 AH						
STA. 64+00.0	TO	STA. 64+35.0	CENTER LINE	SKIP-DASH	35	7 1.2
SPRESSER ST.						
STA. 10+62.0	TO	STA. 11+38.2	CENTER LINE	SKIP-DASH	68	13.6 2.3
NOKOMIS RD.						
STA. 38+59.0	TO	STA. 40+00.0	LANE LINE	SKIP-DASH	141 28.2	4.7
	TO	STA. 39+20.0	LANE LINE	SKIP-DASH	65 13	2.2
SUB TOTAL					404.8	5267.3
TOTAL					5672	944

NOTE: SHORT-TERM PAVEMENT MARKING QUANTITIES ARE FOR TWO APPLICATIONS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
FA ROUTE 714 (IL 48)
SECTION (135)RS-6,TS
CHRISTIAN COUNTY

SCALE: VERT.
 HORIZ.
 DATE

DRAWN BY
 CHECKED BY