

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
753	25 RS-8, 1-2	MORGAN	26	3
STA.		TO STA.		
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				

SUMMARY OF QUANTITIES

80% FED.
20% STATE

CODE NO.	ITEM	UNITS	1000 TOTAL
35800100	PREPARATION OF BASE	SQ YD	858.3
35800200	AGGREGATE BASE REPAIR	TON	23.05
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	24.83
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	52.6
40600300	AGGREGATE (PRIME COAT)	TON	277
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	2887
40600895	CONSTRUCTING TEST STRIP	EACH	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	373.99
40600985	PCC SURFACE REMOVAL - BUTT JOINT	SQ YD	291.02
40600990	TEMPORARY RAMP	SQ YD	364
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4330
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	533
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	1599
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	300
44200948	CLASS B PATCHES, TYPE I, 9 INCH	SQ YD	4
44200956	CLASS B PATCHES, TYPE II, 9 INCH	SQ YD	212
44200962	CLASS B PATCHES, TYPE III, 9 INCH	SQ YD	60
44213100	PAVEMENT FABRIC	SQ YD	60
44213200	SAW CUTS	FOOT	1444
48101200	AGGREGATE SHOULDERS, TYPE B	TON	760
48203100	HOT-MIX ASPHALT SHOULDERS	TON	2855
60402210	GRATES, TYPE B	EACH	1
60405740	FRAMES AND GRATES TO BE REMOVED	EACH	1
60607400	COMBINATION CONCRETE CURB AND GUTTER, TYPE R-9.24	FOOT	533
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	380
64200105	SHOULDER RUMBLE STRIP	FOOT	159
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5
67100100	MOBILIZATION	L SUM	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3305
70100310	TRAFFIC CONTROL AND PROTECTION, STANARD 701421	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANARD 701201	L SUM	1

SUMMARY OF QUANTITIES

80% FED.
20% STATE

CODE NO.	ITEM	UNITS	1000 TOTAL
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	374.4
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	42226
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1726
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1130
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	42
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	50
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	20920
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	11.25
78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	374.4
78003120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 5"	FOOT	3770
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	1726
78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	1130
78003150	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 12"	FOOT	42
78003180	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 24"	FOOT	50
78000220	POLYUREA PAVEMENT MARKING TYPE I - LINE 5"	FOOT	38456
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	198
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	198
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	93
X440A200	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING)	SQ YD	121
20017202	DOWEL BARS, 1 1/2"	EACH	602
20033600	LONGITUDINAL JOINT REPAIR	FOOT	2124
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SD YD	531.75
35300300	PORTLAND CEMENT CONCRETE BASE COURSE 8"	SD YD	531.75
44004250	PAVED SHOULDER REMOVAL	SQ YD	235
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	235
20200100	EARTH EXCAVATION	CU YD	458.6
25000200	SEEDING, CLASS 2	ACRE	0.3
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	27
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	27
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27
25100115	MULCH METHOD 2	ACRE	0.3

• SPECIALTY ITEMS

PLOT DATE : 2/2/2007
 FILE NAME : c:\projects\850785\schedule of quantities.dwg
 PLOT SCALE : 211.7647 / IN
 USER NAME : tleight@ill

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAP RTE 753 SPUR (OLD US 36) & FAS 1613
 SECTION 25RS-8, 1-2
 MORGAN COUNTY

SCALE: VERT.
 HORIZ. NONE
 DATE: OCTOBER 2006

DRAWN BY: LLD
 CHECKED BY: