

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
320	•	MACON	31	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• (10)RS-3, 101B-1				

PAVING SCHEDULE

STATION TO STATION	LENGTH	PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD), N70	HOT-MIX ASPHALT SURF. CSE MIX "D", N70	HOT-MIX ASPHALT SURFACE REMOVAL, 1/2"	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	AGGREGATE SHOULDERS, TYPE B
	FEET	FEET	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	SQ YD	TON
<b>RURAL</b>											
STATION TO STATION											
869+00 TO 870+04	104.2	32	370.5	74.1	1.5	15.6	31.1	370.5	160.0	28.0	5.9
60+45 TO 236+90	17645.0	32	62737.8	12547.6	251.0	2635.0	5270.0	62737.8			1004.8
236+74 TO 264+13	2739.9	32	9741.9	1948.4	39.0	409.2	818.3	9741.9			234.0
<b>URBAN</b>											
265+85 TO 287+32	2146.2	32	7630.9	1526.2	30.5	320.5	641.0	7503.8	160.0	28.0	122.2
<b>TOTALS</b>	<b>22635.3</b>		<b>80481</b>	<b>16096</b>	<b>322</b>	<b>3380</b>	<b>6760</b>	<b>80354</b>	<b>320</b>	<b>56</b>	<b>1367</b>

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING-LINE 4"	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR, REMOVAL	PAINT PAVEMENT MARKING REMOVAL
	FEET	FT	SQ FT	FT	EA	EA	SQ FT
<b>RURAL</b>							
STATION TO STATION							
869+00 TO 870+04	104	31	3	234	1		
60+45 TO 236+90	17645	5294	1247	39701	221	8	444
236+74 TO 264+13	2740	822	91	6165	34		
<b>URBAN</b>							
265+85 TO 287+32	2146	645	71	7033	27		
<b>TOTALS</b>	<b>22635</b>	<b>6792</b>	<b>1412</b>	<b>53134</b>	<b>283</b>	<b>8</b>	<b>444</b>

PATCHING SCHEDULE

LOCATION	PARTIAL DEPTH PATCHING	PARTIAL DEPTH REMOVAL, 3"	PAVEMENT PATCHING, TYPE III, 10 INCH	PAVEMENT PATCHING, TYPE I, 12 INCH	PAVEMENT PATCHING, TYPE II, 12 INCH	PAVEMENT PATCHING, TYPE III, 12 INCH	PAVEMENT PATCHING, TYPE IV, 12 INCH
	TON	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD
URBAN: WB	0.0	0.0	0.0	0.0	48.0	0.0	32.0
URBAN: EB	0.0	0.0	0.0	0.0	0.0	0.0	
RURAL: WB	0.1	347.0	16.0	20.0	222.7	117.3	158.0
RURAL: EB	0.1	306.7	16.0	18.7	165.3	16.0	93.3
<b>TOTALS</b>	<b>0.16</b>	<b>654</b>	<b>32</b>	<b>39</b>	<b>436</b>	<b>133</b>	<b>283</b>

PIPE CULVERT SCHEDULE

STATION	LENGTH	PIPE CULVERT, CLASS A, TY 1, ERS 24"	END SECTION, ERS 24"	TRENCH BACKFILL
	FEET	FT	EACH	CU YD
124+70 TO 168+65	40	40	2	5.0
	40	40	2	5.0
<b>TOTALS</b>	<b>80</b>	<b>80</b>	<b>4</b>	<b>10.0</b>

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SCHEDULES**

SCALE: VERT.  
HORIZ.  
DATE

DRAWN BY  
CHECKED BY