

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	82-(1,2,3,4)RS-1	ST CLAIR	43	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

PAVEMENT MARKING SCHEDULE														
LOCATION			PREF PL TB INL					SHORT - TERM			WORK ZONE PAVT MK REM (SQ FT)	RAISED REFL PAVT MKR		RAISED REF PVT MK REM (EA)
			4"		8"			4"				ONE WAY CRYSTAL (EA)	ONE WAY AMBER (EA)	
			SOLID WHITE (FT)	SOLID YELLOW (FT)	SPECIAL SKIP-DASH WHITE (FT)	SOLID YELLOW (FT)	SOLID WHITE (FT)	EDGE LINE WHITE (FT)	EDGE LINE YELLOW (FT)	SKIP DASH WHITE (FT)				
STA	TO	STA	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(FT)	(EA)	(EA)	(EA)	
ROADWAY C - EASTBOUND														
80+37.83	TO	83+29.34	291.5	291.5	72.9			11.7	11.7	29.2	17.3	7		7
86+08.06	TO	98+15.39	1207.3	1207.3	301.8			48.3	48.3	120.7	71.7	30		30
101+81.33	TO	103+89.35	208.0	208.0	104.0		416.0	8.3	8.3	41.6	19.2	10		10
10+49.3	TO	16+63.36	614.1	614.1	307.0			24.6	24.6	122.8	56.7	31		31
19+11.57	TO	22+20.48	308.9	308.9	154.5			12.4	12.4	61.8	28.5	15		15
23+09.91	TO	32+32.25	922.3	922.3	461.2			36.9	36.9	184.5	85.2	46		46
33+27.59	TO	46+18.95	621.4	1291.4	645.7		670.0	51.7	51.7	258.3	119.3	82		82
46+18.95	TO	51+00.	481.1	281.1	360.8		200.0	19.2	19.2	144.3	60.3	23		23
51+00.	TO	59+44.95	845.0	845.0	845.0			33.8	33.8	338.0	133.8	84		84
59+44.95	TO	81+27.84	1832.9	1832.9	1091.4	350.0	350.0	8745.6	8745.6	436.6	5916.1	55		55
81+27.84	TO	93+13.	985.2	1185.2	592.6		674.1	47.4	47.4	3674.0	1243.7	64		64
ROADWAY B - WESTBOUND														
92+60.	TO	86+46.42	113.6	613.6	552.2		350.0	24.5	24.5	184.1	76.9	40		40
86+46.42	TO	62+50.1	2396.3	1496.3	1557.6		900.0	95.9	95.9	479.3	221.4	83		83
61+76.9	TO	55+00.	676.9		169.2		677.0	27.1	27.1	101.5	51.4	34		34
55+00.	TO	51+73.59	326.4		244.8		326.0	13.1	13.1	97.9	40.9	32		32
51+73.59	TO	40+63.25	1110.3	1110.3	1110.3			44.4	44.4	444.1	175.9	111		111
40+63.25	TO	9+77.42	3085.8	3085.8	1542.9		205.0	123.4	123.4	617.2	285.1	77		77
101+71.14	TO	99+46.96	224.2	224.2	56.0			9.0	9.0	22.4	13.3	6		6
96+09.13	TO	85+40.39	1068.7	1068.7	267.2			42.7	42.7	320.6	134.0	53		53
83+14.73	TO	79+48.83	365.9	365.9	329.3			14.6	14.6	36.6	21.7	9		9
EB I-64														
39+53.37	TO	50+09.79	1056.4	1056.4	264.1			42.3	42.3	105.6	62.8	29		29
WB I-64														
37+68.35	TO	31+00.	168.4	668.4			500.0	26.7	26.7		17.6	13		13
RAMPS														
RAMP D														
36+07.28	TO	42+00.		492.7	148.2		100.0		23.7	59.3	27.4	18		18
40+00.	TO	43+24.88					325.0			32.5	10.7	8		8
39+83.65	TO	43+24.88	341.2					13.6			4.5			
43+24.88	TO	46+18.95	294.1	194.1	73.5		100.0		11.8	29.4	13.6	10		10
EB MLK APPROACH														
43+24.88	TO	51+00.	575.1	675.1			200.0		31.0	77.5	35.8	24		24
RAMP J														
7+15.	TO	14+15.9	500.9	700.9			200.0			51.5	17.0	5		5
RAMP M														
2+63.98	TO	6+44.18	380.2	280.2			100.0	15.2	15.2		10.0	3		3
RAMP N														
19+11.24	TO	29+03.73	992.5	692.5			300.0	39.7	39.7		26.2	8		8
RAMP P														
1+00.	TO	6+19.81	519.8	219.8			300.0	20.8	20.8		13.7	8		8
6+19.81	TO	10+16.96	397.2					15.9			5.2			
RAMP O														
0+00	TO	1+49.35		149.0	37.3				6.0	14.9	6.9			
1+49.35	TO	7+28.	578.7	178.7			400.0	11.1	23.1	30.0	21.2	8		8
APPROACH TO RAMPS K & L														
79+30.14	TO	83+95.14	215.0	465.0			250.0	8.6	18.6		9.0	7		7
RAMP I														
10+13.01	TO	12+37.73		224.7			225.0	9.0	9.0		5.9	6		6
RAMP 2														
+78.71	TO	4+33.05	354.3				354.3	14.2		35.4	16.4	9		9
WB MLK APPROACH														
40+63.25	TO	38+78.37		184.9			184.9		7.4	18.5	8.5	5		5
RAMP A														
10+00.	TO	13+23.67		323.7			129.5		12.9	32.4	15.0			
13+23.67	TO	14+61.42	37.8	137.8			100.0	5.5	5.5		3.6	3		3
TOTALS			24097	23596	11290	350.0	8537	9657	9728	8202	9104	1059	0	1059

NOTE: QUANTITY FOR TEMPORARY PAVEMENT MARKING - LINE 4" AND 8" EQUALING ALL PREFORMED PLASTIC PAVEMENT MARKING HAS BEEN INCLUDED IN THE SUMMARY OF QUANTITIES

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p align="center">SCHEDULES</p> <p align="center">FAI 55/70/64 SECTION 82-(1,2,3,4)RS-1 ST CLAIR COUNTY</p> <p>SCALE: VERT. DRAWN BY HORIZ. CHECKED BY</p>

PLT DATE = 2/16/2007
FILE NAME = c:\pavement\82-1,2,3,4\rs-1\plan\p148-307.dwg
PLOT SCALE = 1/8"=1'-0" / IN.
REFERENCE = #REF#