

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
809	67-1HB-MCHD-1	MONROE	9	2
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

ILLINOIS DEPARTMENT OF TRANSPORTATION

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT	100% MCHD URBAN TOTAL QUANTITIES	SFTY-2A
50102400	CONCRETE REMOVAL	CU YD	1.3	1.3
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1.3	1.3
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	6610	6610
50501110	STRUCTURAL STEEL REMOVAL	POUND	6610	6610
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1
70101800	TRAFFIC CONTROL AND PROTECTION (SPECIAL)	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1	1
70400100	TEMPORARY CONCRETE BARRIER	FOOT	225	225
X7010825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701423 (SPECIAL)	L SUM	1	1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1	1
Z0073351	TEMPORARY SLAB SUPPORT SYSTEM	L SUM	1	1

## INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS, GENERAL NOTES, STANDARDS & SUMMARY OF QUANTITIES
- 3-4 TRAFFIC CONTROL PLAN
- 5 MISCELLANEOUS DETAILS
- 6-9 BRIDGE REPAIR PLANS

## GENERAL NOTES

1. THE STANDARDS AND REVISION NUMBERS LISTED SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
  - CHARTER COMMUNICATIONS, INC.
  - CITY OF COLUMBIA - WATER & SEWER
  - HARRISONVILLE TELEPHONE CO.
  - ILLINOIS AMERICAN WATER COMPANY
  - AMERENIP
 (MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY \*. NON-J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.)
4. NO SURVEY WAS PERFORMED FOR THIS PROJECT. THE STATIONING, TOPOGRAPHY, ETCETERA SHOWN IS APPROXIMATE AND WAS CREATED USING MICROFILM.
5. ONE CHANGEABLE MESSAGE SIGN SHALL BE REQUIRED ON THE PROJECT. THE MESSAGE SIGN SHALL BE PLACED ONE WEEK BEFORE ANY LANE RESTRICTION. THE MESSAGE SIGN SHALL BE PLACED AT NORTHBOUND IL 3, NEAR THE NORTH EDGE OF WATERLOO, OR AS DIRECTED BY THE ENGINEER.
6. NO OVERNIGHT LANE CLOSURES WILL BE PERMITTED ON IL 3.
7. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED AT THE BEGINNING AND END OF THE PROJECT PLUS THE INTERSECTING SIDEROADS, AND WILL BE CONSIDERED INCLUDED IN THE TRAFFIC CONTROL PAY ITEMS. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE.
8. NEW JERSEY (NJ) SHAPE BARRIER WILL BE ALLOWED ON THIS PROJECT. INSTALLATION SHALL BE AS SHOWN ON THE PLANS.
9. THE CONTRACTOR SHOULD INSURE THAT, IN AND ADJACENT TO WORK AREAS, ALL LOOSE, SPALLED AND DELAMINATED CONCRETE IS REMOVED PRIOR TO REOPENING LANES TO TRAFFIC. THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE CONSIDERED INCIDENTAL TO "CONCRETE REMOVAL".

## STANDARDS

- 000001-04
- 701411-03
- 701421-01
- 701423-01
- 702001-06
- 704001-03

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**INDEX OF SHEETS, GENERAL NOTES,  
 STANDARDS &  
 SUMMARY OF QUANTITIES**  
 FAP ROUTE 809 (IL 158)  
 SECTION 67-1HB-MCHD-1  
 MONROE COUNTY

PLOT DATE = 2/6/2007  
 FILE NAME = c:\projects\4865987\plan\010507.dgn  
 PLOT SCALE = 48,9999 / IN.  
 REFERENCE = #REF#