F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
---	06-00061-00-SW	COOK	37	3
STA. ---		TO STA. ---		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 83899

SUMMARY OF QUANTITIES

LOCATION OF WORK				PCC SIDEWALK					
				FULLERTON AVE. 80% FED. 20% LOCAL	HARVARD AVE. 80% FED. 20% LOCAL	NORTH AVE. 80% FED. 20% LOCAL	PALMER AVE. 80% FED. 20% LOCAL	PALMER AVE. 80% FED. 20% LOCAL	WILTSE DR. 80% FED. 20% LOCAL
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
ITEM #	ITEM	UNIT	TOTAL QUANTITIES	SFTY-1B	SFTY-1B	SFTY-1B	SFTY-1B	I000	SFTY-1B
*20101200	TREE ROOT PRUNING	EACH	6	0	1	0	2	0	3
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CY	340	85	40	30	115	0	70
20400800	FURNISHED EXCAVATION	CY	30	2	15	2	10	0	1
20800150	TRENCH BACKFILL	CY	12	10	2	0	0	0	0
*25000210	SEEDING, CLASS 2A	ACRE	1.15	0.3	0.2	0.15	0.25	0	0.25
*25000400	NITROGEN FERTILIZER NUTRIENT	POUND	103.5	27	18	13.5	22.5	0	22.5
*25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	103.5	27	18	13.5	22.5	0	22.5
*25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	103.5	27	18	13.5	22.5	0	22.5
*25100630	EROSION CONTROL BLANKET	SY	3900	1100	675	350	1000	0	775
*25200200	SUPPLEMENTAL WATERING	UNIT	50	10	10	10	10	0	10
*28000300	TEMPORARY DITCH CHECKS	EACH	3	0	0	0	3	0	0
*28000400	PERIMETER EROSION BARRIER	FOOT	1799	370	32	0	837	0	560
*28000510	INLET FILTERS	EACH	13	3	2	2	2	0	4
31101100	SUB-BASE GRANULAR MATERIAL, TYPE B	CY	181	66	38	12	38	0	27
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SY	255	190	50	0	0	0	15
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	285	100	100	10	25	0	50
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 (QC/QA)	TON	25	0	0	0	0	25	0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50 (QC/QA)	TON	78	35	10	0	0	30	3
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH (HIGH EARLY)	SY	40	0	40	0	0	0	0
42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SF	17650	4535	2905	1575	5070	0	3565
42400300	PORTLAND CEMENT CONCRETE SIDEWALK, 6 INCH	SF	915	545	295	0	0	0	75
42400800	DETECTABLE WARNINGS	SF	300	60	70	20	130	0	20
44000100	PAVEMENT REMOVAL	SY	42	0	0	0	0	42	0
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SY	160	0	0	0	0	160	0
44000200	DRIVEWAY PAVEMENT REMOVAL	SY	421	265	135	0	0	0	21
44000600	SIDEWALK REMOVAL	SF	520	45	150	0	170	0	155
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	630	120	110	30	45	250	75
550B0030	STORM SEWER CLASS B, TYPE 1, 8"	FOOT	10	10	0	0	0	0	0
60207605	CATCH BASINS, TYPE C, TYPE 8 GRATE	EACH	2	1	1	0	0	0	0
60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	4	1	3	0	0	0	0
60255500	MANHOLES TO BE ADJUSTED	EACH	2	1	0	1	0	0	0
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	1	0	0	0	1	0	0
63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	112.5	0	0	0	112.5	0	0
63200310	GUARDRAIL REMOVAL	FOOT	135	0	0	0	135	0	0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L. SUM	1	0.2	0.2	0.2	0.1	0.1	0.2
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L. SUM	1	0.2	0.2	0.2	0.1	0.1	0.2
*72000100	SIGN PANEL -TYPE 1	SF	12.5	0	0	0	0	12.5	0
*72900100	METAL POST - TYPE A	FOOT	28	0	0	0	0	28	0
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	341	225	56	0	60	0	0
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	40	0	0	0	0	40	0
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	67	40	15	0	12	0	0
X0322124	STORM SEWER (WATER MAIN REQUIREMENTS) 8 INCH	FOOT	10	0	10	0	0	0	0
*X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	13	3	2	2	2	0	4
XX004774	BRICK DRIVEWAY REMOVAL AND REPLACEMENT	SF	100	0	100	0	0	0	0
*XX005238	TOPSOIL FURNISH AND PLACE,VARIABLE DEPTH	CY	125	15	50	15	35	0	10
Z0013798	CONSTRUCTION LAYOUT	L. SUM	1	0.2	0.2	0.2	0.1	0.1	0.2
67100100	MOBILIZATION	L.SUM	1	0.2	0.2	0.2	0.1	0.1	0.2

* INDICATES SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CITY OF NORTHLAKE - CMAQ SIDEWALKS

SCALE

DRAWN BY AMP

DATE 01/04/2007

CHECKED BY MW

CHRISTOPHER B. BURKE ENGINEERING LTD.
9575 West Higgins Road, Suite 600
Rosemont, Illinois 60018
(847) 823-0500

PLAN | SURVEYED | PLATTED | ALIGNMENT CHECKED | R.O.W. CHECKED | FIELD FILE NAME | NOTE BOOK NO. | BY | DATE

PROFILE | SURVEYED | PLATTED | GRADES CHECKED | B.M. NOTED | STRUCTURE | NOTE BOOK NO. | BY | DATE

01/04/2007 N:\NORTHLAKE\94520055\Civil\dc65_soql.pln