COUNTY

DETAILS

ILLINOIS


TOTAL SHEETS


36

13

SECTION

1340 06-00048-00-RS COOK






NOTE.

- SET 3/4" EXPANSION JOINTS AT POINTS ABUTTING CURB OR PAVEMENT AND AT 45" MAX. INTERVALS.
- CONTROL JOINTS SHALL BE 1/8" TO 1/4" WIDE AND 1/4 OF THE SIDEWALK THICKNESS DEEP. THE EDGE OF THE CONTROL JOINTS SHALL BE GIVEN A 1/4" RADIUS.
- 3. TWO #5 DEFORMED STEEL BARS SHALL BE INSTALLED IN THE SIDEWALK CENTERED OVER ALL TRENCH CROSSINGS. THEY SHALL EXTEND 10 FEET BEYOND THE EDGES OF THE TRENCH.

PCC SIDEWALK 8"



SET 3/4" WHITE EPOXY EXPANSION JOINTS AT POINTS ABUTTING CURB OR PAYEMENT AND AT 60" MAX. INTERVALS.

 CONTROL JOINTS SHALL BE 1/8" TO 1/4" WIDE AND 1/4 OF THE SIDEWALK THICKNESS DEEP. THE EDGE OF THE CONTROL JOINTS SHALL BE GIVEN A 1/4" RADIUS.

- 3. SIDEWALK WIDTH AS SHOWN ON PLANS.
- 3. ALL STEEL BARS SHOWN ARE EPOXY COATED

PCC SIDEWALK 5" (ADJACENT TO BUILDINGS)

