

TRENCH BACKFILL SCHEDULE		
LOCATION	TRENCH BACKFILL SPECIAL (CU YD)	
SECTION 01-00017-00-FP		
STA 199+54	114	WALDRON
STA 9+85 TO 9+90	15	LOWE
STA 10+31 TO 10+62 - 25 LT	71	DRIVE
STA 11+05	6	LOWE
STA 11+15 TO 11+46 - 25' LT	74	DRIVE
STA 12+00	8	LOWE
STA 12+66 TO 12+91 - 25' LT	64	DRIVE
STA 13+50	8	LOWE
STA 13+96 TO 14+82 - 25' LT	134	OLD WALDRON
STA 14+85	6	LOWE
STA 14+78 TO 18+10 - 25 LT	535	SIDEWALK
STA 18+10	5	LOWE
STA 18+26 TO 18+38 - 31 RT	5	SIDEWALK
STA 18+42 - 41 TO 51 RT	3	DRIVE
STA 18+26 TO 15+99 - 25 LT	152	DRIVE
STA 17+20	12	LOWE
STA 18+93 TO 17+03 - 30 RT	6	SIDEWALK
STA 17+48 TO 17+75 - 25 LT	51	DRIVE
STA 18+34 TO 18+64 - 25 LT	98	DRIVE
STA 19+32 TO 19+59 - 25 LT	94	DRIVE
STA 20+14 TO 20+90 - 25 LT	181	RICHARD
STA 21+90	8	LOWE
STA 22+31 TO 22+54 - 25 LT	69	DRIVE
STA 22+66 TO 23+82 - 25 LT	330	SIDEWALK
STA 23+15	8	LOWE
STA 24+07 TO 24+32 - 25 LT	67	DRIVE
STA 24+70	8	LOWE
STA 24+77 TO 25+00 - 25 LT	58	DRIVE
STA 25+85 TO 25+88 - 25 LT	51	DRIVE
STA 25+98 TO 26+18 - 25 LT	41	DRIVE
STA 26+40 TO 26+60 - 25 LT	37	DRIVE
STA 26+85	8	LOWE
STA 27+23 TO 27+50 - 25 LT	41	DRIVE
STA 28+20	8	LOWE
STA 28+22 TO 28+49 - 25 LT	36	DRIVE
STA 28+69 TO 28+74 - 31 LT	3	SIDEWALK
STA 28+86 TO 29+40 - 25 LT	56	STRASMA
STA 29+75	10	LOWE
STA 30+14 TO 30+41 - 25 LT	11	DRIVE
STA 30+60 TO 32+84 - 25 LT	87	SIDEWALK
STA 31+00	6	LOWE
STA 33+00	6	LOWE
STA 195+60 TO 196+00 - 25 RT	74	DRIVE
STA 200+29 TO 200+38 - 29 LT	14	SIDEWALK
STA 201+55	15	WALDRON
STA 201+55 - 32 LT	3	SIDEWALK
STA 202+86 TO 202+95 - 25 RT	12	SIDEWALK
STA 203+00	25	WALDRON
STA 202+95 - 32 LT	10	SIDEWALK
STA 205+89 TO 206+25 - 19 LT	13	DRIVE
STA 206+35	12	WALDRON
STA 207+70	5	WALDRON
STA 301+58	12	IRVINE
STA 301+74 TO 301+92 - 21 RT	4	DRIVE
SUBTOTAL	2676	
SECTION 02-00284-00-WR		
STA 63+70 TO 64+30 - 29 LT	18	DAY
STA 64+25	19	LOWE
STA 80+18 TO 80+78 - 27 LT	10	POTTENGER
STA 84+00	19	LOWE
STA 142+15 TO 144+75 - 28 RT	67	SHOULDER
SUBTOTAL	133	
TOTAL	2809	

NON-SPECIAL WASTE SCHEDULE	
LOCATION	NON-SPECIAL WASTE DISPOSAL (CU YD)
SECTION 01-00017-00-FP	
STA 201+75 TO 202+25 LT	100
SUBTOTAL	100
SECTION 02-00284-00-WR	
SUBTOTAL	0
TOTAL	100

CONDUIT SCHEDULE	
LOCATION	CONDUIT IN TRENCH 3" DIA, PVC (FOOT)
SECTION 01-00017-00-FP	
STA 207+70	40
SUBTOTAL	40
SECTION 02-00284-00-WR	
SUBTOTAL	0
TOTAL	40

RETAINING WALL SCHEDULE	
LOCATION	MODULAR BLOCK RETAINING WALL (SQ FT)
SECTION 01-00017-00-FP	
STA 15+50 TO 15+63 RT	42
SUBTOTAL	42
SECTION 02-00284-00-WR	
SUBTOTAL	0
TOTAL	42

PAVEMENT MARKING SCHEDULE							
LOCATION	TEMPORARY PAVEMENT MARKING LINE 4" (FOOT)	THERMOPLASTIC PAVEMENT MARKING			RECESSED REFLECTIVE PAVEMENT MARKER (EACH)	PAVEMENT MARKING REMOVAL (SQ FT)	
		LETTERS AND SYMBOLS (SQ FT)	LINE 6" (FOOT)	LINE 12" (FOOT)			
SECTION 01-00017-00-FP							
STA 9+50 TO 36+50	680					227	SKIP DASH YELLOW
STA 9+50 TO 36+50			680		68		SKIP DASH YELLOW
STA 9+59			96	90			CROSS WALK WHITE
STA 9+75					28		STOP BAR WHITE
STA 14+01			70	60			CROSS WALK WHITE
STA 14+30 LT			76	60			CROSS WALK WHITE
STA 14+30 LT					15		STOP BAR WHITE
STA 18+34			67	60			CROSS WALK WHITE
STA 18+85 RT			88	78			CROSS WALK WHITE
STA 18+85 RT					17		STOP BAR WHITE
STA 20+19			72	60			CROSS WALK WHITE
STA 20+48 LT			88	84			CROSS WALK WHITE
STA 20+48 LT					17		STOP BAR WHITE
STA 29+00 LT			82	72			CROSS WALK WHITE
STA 29+00 LT					17		STOP BAR WHITE
STA 29+33			66	60			CROSS WALK WHITE
STA 31+71 RT		61.2			28		RR CROSSING WHITE
STA 197+50 TO 208+00	260					87	SKIP DASH YELLOW
STA 197+50 TO 208+00			280		26		SKIP DASH YELLOW
STA 200+32			54	48			CROSS WALK WHITE
STA 202+92			56	48			CROSS WALK WHITE
STA 301+32			56	48			CROSS WALK WHITE
STA 301+48					13		STOP BAR WHITE
SUBTOTAL	940	61.2	1811	768	131	94	314
SECTION 02-00284-00-WR							
STA 36+86 TO 151+50	2870					957	SKIP DASH YELLOW
STA 36+50 TO 151+50					267		
STA 36+50 TO 151+50			2870				SKIP DASH YELLOW
STA 36+86 TO 151+50 LT			11484				EDGE LINE WHITE
STA 36+86 TO 151+50 RT			11484				EDGE LINE WHITE
STA 41+27 LT		61.2			24		RR CROSSING WHITE
STA 54+00 RT					12		STOP BAR WHITE
STA 80+48 LT					12		STOP BAR WHITE
STA 127+45 TO 135+83			838				LINE YELLOW
STA 138+42 TO 147+07			865				LINE YELLOW
SUBTOTAL	2870	61.2	27541	0	48	287	957
LESS COUNTY	-2870	0	-27541	0	-24	0	-957
TOTAL	940	122.4	1811	768	155	381	314

* TO BE DONE BY KANKAKEE COUNTY FORCES

FENCING SCHEDULE				
LOCATION	CHAIN LINK GATE 6"x6" DOUBLE (EACH)	FENCE TO BE REMOVED AND RE-ERECTED (FOOT)	SPLIT RAIL FENCE TO BE REMOVED AND RE-ERECTED (FOOT)	WOODEN FENCE RELOCATION (FOOT)
SECTION 01-00017-00-FP				
STA 21+89 TO 22+33 - 35 LT			44	
STA 22+49 TO 23+21 - 35 LT			72	
STA 23+47 TO 24+08 - 35 LT			61	
STA 34+25 - 40 RT	1			
STA 203+12 TO 203+25 - 35 LT				13
SUBTOTAL	1	0	177	13
SECTION 02-00284-00-WR				
STA 37+15 TO 44+15 - 33 RT		700		
STA 45+20 TO 46+42 - 33 RT		122		
SUBTOTAL	0	822	0	0
TOTAL	1	822	177	13

TURF ESTABLISHMENT SCHEDULE				
LOCATION	TOPSOIL FURNISH AND PLACE 4" (SQ YD)	SEEDING CLASS 2A (ACRE)	MULCH METHOD 3 (ACRE)	SODDING SALT TOLERANT (SQ YD)
SECTION 01-00017-00-FP				
STA 9+50 TO 11+10	263			263
STA 11+10 TO 14+30	1060			1060
STA 14+30 TO 20+16	1700			1700
STA 20+16 TO 32+80	1667	0.40	0.40	1667
STA 32+80 TO 36+50	108	0.30	0.30	108
STA 191+00 TO 197+50		0.40	0.40	
STA 197+50 TO 199+25		0.15	0.15	
STA 199+25 TO 200+30		0.05	0.05	
STA 200+30 TO 208+12	994	0.35	0.35	994
STA 301+34 TO 302+30	244			244
SUBTOTAL	6036	1.65	1.65	6036
SECTION 02-00284-00-WR				
STA 36+66 TO 47+00		0.75	0.75	
STA 47+00 TO 54+35		0.85	0.85	
STA 54+35 TO 67+00		1.10	1.10	
STA 67+00 TO 76+00		0.90	0.90	
STA 76+00 TO 77+65	398			398
STA 77+65 TO 120+00		4.85	4.85	
STA 120+00 TO 142+25		2.15	2.15	
STA 142+25 TO 151+70		0.80	0.80	
SUBTOTAL	398	11.00	11.00	398
TOTAL	6434	12.65	12.65	6434

SIDEWALK SCHEDULE		
LOCATION	PORTLAND CEMENT CONCRETE SIDEWALK 4" (SQ FT)	DETECTABLE WARNING (SQ FT)
SECTION 01-00017-00-FP		
STA 9+76 TO 32+64 LT	8740	63
STA 13+98 TO 14+60 RT	108	0
STA 14+00	100	18
STA 15+06 TO 15+68 RT	160	0
STA 16+21 TO 17+35 RT	256	18
STA 16+34	113	9
STA 17+85 TO 18+32 RT	124	0
STA 20+20	90	9
STA 26+26 TO 29+39 RT	400	0
STA 29+26	170	0
STA 29+37	105	18
STA 200+05 TO 207+84 LT	3230	27
STA 200+25 TO 208+31 RT	4030	0
STA 200+25	175	18
STA 202+90	145	18
SUBTOTAL	17946	198
SECTION 02-00284-00-WR		
SUBTOTAL	0	0
TOTAL	17946	198

GUARD RAIL SCHEDULE					
LOCATION	STEEL PLATE BEAM GUARD RAIL TYPE A (FOOT)	TRAFFIC BARRIER TERMINAL TYPE 5A (EACH)	TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (TANGENT) (EACH)	GUARDRAIL REFLECTORS (EACH)	TERMINAL MATERIALS - DIRECT APPLIED (EACH)
SECTION 01-00017-00-FP					
SUBTOTAL	0	0	0	0	0
SECTION 02-00284-00-WR					
STA 108+60 TO 111+40 RT	137.5	2	2	3	2
STA 108+85 TO 111+70 LT	137.5	2	2	3	2
SUBTOTAL	275	4	4	6	4
TOTAL	275	4	4	6	4

EXCAVATION SCHEDULE				
LOCATION	EARTH EXCAVATION (CU YD)	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)	FURNISHED EXCAVATION	ROCK EXCAVATION FOR STRUCTURES (CU YD)
SECTION 01-00017-00-FP				
STA 9+90 TO 24+80				2090
STA 191+00 TO STA 208+00	3574			WALDRON
STA 10+00 TO STA 36+50	5044	4738		LOWE
SUBTOTAL	8618	4738	0	2090
SECTION 02-00284-00-WR				
BRIDGE				15
STA 36+66 TO STA 151+50	9881	7875	1188	LOWE
SUBTOTAL	9881	7875	1188	15
TOTAL	18499	12613	1188	2105

STRIP REFLECTIVE CRACK CONTROL SCHEDULE	
LOCATION	STRIP REFLECTIVE CRACK CONTROL TREATMENT SYSTEM A (FOOT)
SECTION 01-00017-00-FP	
SUBTOTAL	0
SECTION 02-00284-00-WR	
STA 38+00 TO 106+50	13700
STA 113+00 TO 134+50	4300
STA 138+00 TO 151+50	2700
SUBTOTAL	20700
TOTAL	20700

TREES SCHEDULE			
LOCATION	REMOVAL (6 TO 15 UNITS) (UNITS)	(OVER 15 UNITS) (UNITS)	GREEN ASH 2" CALIPER (EACH)
SECTION 01-00017-00-FP			
203+00 - 32 LT		36	
301+41 - 40 RT			1
26+30 - 20 LT			1
26+38 - 29 LT	8		
34+05 - 30 RT			1
34+19 - 38 RT	8		
SUBTOTAL	16	36	3
SECTION 02-00284-00-WR			
57+55 - 35 LT			1
58+00 - 30 LT	12		
75+80 - 25 RT	8		
76+40 - 40 LT			1
76+40 - 35 RT			1
76+43 - 27 LT		24	
76+78 - 20 LT	15		
76+80 - 24 RT	12		
76+90 - 35 RT			1
77+63 - 23 RT		18	
77+90 - 40 LT			1
78+00 - 40 LT			1
85+05 - 17 RT	10		
85+05 - 27 RT			1
85+13 - 31 RT	8		
87+05 - 27 RT			1
SUBTOTAL	65	42	8
TOTAL	81	78	11

CONTRACT NO. 87314
 FED. ROAD DIST. NO. ILLINOIS
 ** LOWE RD. FAU 6209/WALDRON RD. FAU 5184
 * 02-00284-00-WR & 01-00017-00-FP

TYSON ENGINEERING, INC.
 CONSULTING CIVIL ENGINEERS
 LAND SURVEYORS
 DESIGN FIRM LICENSE #184-001136
 367 SOUTH SCHUYLER AVENUE
 KANKAKEE, ILLINOIS 60901
 PHONE (815) 932-7406

This document and the ideas and designs incorporated herein, as an instrument of professional service, is the property of Tyson Engineering Inc. and is not to be used in whole or in part, for any other project without written authorization of Tyson Engineering Inc.

Do not scale drawings. Use dimensions only.
 Contractor shall be responsible for verifying all dimensions.
 Information herein and herein is confidential.

REVISIONS

NO.	DATE	BY	DESCRIPTION
3	10/24/06	MRG	PER IDOT REVIEW
4	12/29/06	MRG	PER COUNTY REV

SCHEDULE OF QUANTITIES

PROPOSED IMPROVEMENTS FOR
LOWE ROAD
 FROM IL-17 TO WALDRON ROAD
WALDRON ROAD
 FROM CORP. LIMITS TO DIVISION STREET

SECTION 02-00284-00-WR & 01-00017-00-FP