

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ROUTE NO.	DISTRICT	COUNTY	SHEET	TOTAL SHEETS
		Tazewell	43	3
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT	
# 03-00123-03-BT		CONTRACT # 89302		


SUMMARY OF QUANTITIES

Y047

CODE NO.	PAY ITEM	UNIT	SPECIAL PROVISION	SECTION A TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	001N	104
20400800	FURNISHED EXCAVATION	CU YD	001N	109
20800150	TRENCH BACKFILL	CU YD	001N	2.7
25000200	SEEDING, CLASS 2	ACRE	001N	0.02
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	001N	2
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	001N	2
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	001N	2
25100115	MULCH, METHOD 2	ACRE	001N	0.02
28000400	PERIMETER EROSION BARRIER	FOOT	001N	980
28000500	INLET AND PIPE PROTECTION	EACH	001N	1
35100500	AGGREGATE BASE COURSE, TYPE A 6"	SQ YD	001N	772
40603305	HOT-MIX ASPHALT SURFACE COURSE, SUPERPAVE, MIX "C", N30	TON	001N	238
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	001N	1,259
44000100	PAVEMENT REMOVAL	SQ YD	001N	120
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	001N	149
44000600	SIDEWALK REMOVAL	SQ FT	001N	653
48101200	AGGREGATE SHOULDERS, TYPE B	TON	001N	74
50200100	STRUCTURE EXCAVATION	CU YD	001N	28
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	001N	12
* 56400400	FIRE HYDRANTS TO BE RELOCATED	EACH	001Y	1
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	001N	1
60250200	CATCH BASINS TO BE ADJUSTED	EACH	001N	1
60255500	MANHOLES TO BE ADJUSTED	EACH	001Y	2
60260400	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	001N	1
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	001N	141
67100100	MOBILIZATION	L SUM	002N	1
72000100	SIGN PANEL - TYPE 1	SQ FT	002N	34.25
72500200	OBJECT MARKER - TYPE 2	EACH	002N	4
73000100	WOOD SIGN SUPPORT	FOOT	002N	123.5
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	002N	623
* 78300505	PAINT PAVEMENT MARKING REMOVAL	FOOT	002Y	332
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	015Y	1,354
X0006800	CLEANING & PAINTING METAL STRUCTURES	L SUM	015Y	1
* X8440110	RELOCATE EXISTING LIGHT POLE WITH LUMINAIRE	EACH	015Y	2
XX001472	WOOD BOLLARD	EACH	014Y	4
XX003567	FURNISH & INSTALL COLLAPSIBLE STEEL BOLLARD	EACH	014Y	2
XX003949	CONSTRUCTION STAKING	L SUM	014Y	1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	Y	1
* X0006857	ELECTRIC BOX TO BE ADJUSTED	EACH	Y	2
X0006858	RAILING	FOOT	Y	209
X0006859	VALVES TO BE ADJUSTED	EACH	Y	1

* SPECIALTY ITEMS

SUMMARY OF QUANTITIES
BIKE TRAIL OVER FARM CREEK
SECTION 03-00123-03-BT
TAZEWELL COUNTY

DESIGNED RMB	 RANDOLPH & ASSOCIATES, INC. <small>111 N. PINEBUSH, DECATUR, IL 62521-1111 TEL: 312-409-8800 FAX: 312-409-8801 1111 N. PINEBUSH, DECATUR, IL 62521-1111 CONSULTING ENGINEERS & LAND SURVEYORS</small>	FILE NUMBER 56.46
CHECKED CWB		DATE August 2003
DESIGNED RMB		
CHECKED CWB		