F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6998	99-00209-01-PV	VERMILION	296	21
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT-		

CONTRACT NO.: 91358

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	MINOR ARTERIAL ROADWAY FEDERAL I000-2A	BRIDGE S.N. 092-6039 GCPF FEDERAL X631-2A
50200100	STRUCTURE EXCAVATION	CU YD	784.8		784.8
50300225	CONCRETE STRUCTURES	CU YD	242.1	1.7	240.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	41		41
50300300	PROTECTIVE COAT	SQ YD	36	12	24
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	214200	170	214030
50800515	BAR SPLICERS	EACH	146		146
50901720	BICYCLE RAILING	FOOT	54.8	19.3	35.5
50901725	BICYCLE RAILING, SPECIAL	FOOT	83.1	83.1	
50901760	PIPE HANDRAIL	FOOT	284		284
51100100	SLOPE WALL 4 INCH	SQ YD	484		484
51500100	NAME PLATES	EACH	1		1
51603000	DRILLED SHAFT IN SOIL	CU YD	955.0		955.0
54207159	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	FOOT	17	17	
54213450	END SECTIONS 15"	EACH	12	12	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	1		1
54214503	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 18"	EACH	2	2	
54214719	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND-SIZE 24"	EACH	2	2	
5421D015	PIPE CULVERTS, CLASS D, TYPE 1 15" (TEMPORARY)	FOOT	110	110	
54248510	CONCRETE COLLAR	CU YD	0.9	0.9	
542A5473	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	41	41	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	252	252	
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	1346	1121	225
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	231	231	
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	112	112	
55021600	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 12"	FOOT	31	31	
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	41	41	
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	44	44	
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	481	481	
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	29	29	
550A2330	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 15"	FOOT	42	42	
550A2340	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 18"	FOOT	13	13	
550A2520	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 12"	FOOT	90	90	
550A2540	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 18"	FOOT	92	92	
55100500	STORM SEWER REMOVAL 12"	FOOT	41	41	
58000110	MEMBRANE WATERPROOFING (SPECIAL)	SQ FT	5649		5649
58700300	CONCRETE SEALER	SQ FT	1198		1198
60100945	PIPE DRAINS 12"	FOOT	56	56	
60101805	PIPE DRAINS 8" (SPECIAL)	FOOT	22		22
60109584	PIPE UNDERDRAINS FOR STRUCTURES 8"	FOOT	60		60
60218400	MANHOLES, TYPE A, 4' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	16	13	3
60221100	MANHOLES, TYPE A, 5' - DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4	
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	42	39	3
60238700	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH	5	5	
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	21	16	5

PLAN | SURVEYED | ROUTED | ALIGNMENT CHECKED | RT/WAY CHECKED | CADD FILE NAME | NOTE BOOK NO. | BY | DATE

REVISIONS NAME	DATE

CITY OF DANVILLE, ILLINOIS

WINTER AVENUE RECONSTRUCTION

SUMMARY OF QUANTITIES

SCALE: DATE: 02/07/07

DRAWN BY: MBF CHECKED BY: SMK