

DATE _____ BY _____
 SURVEYED _____ PLOTTED _____
 PLAN _____ CHECKED _____
 NO. _____ RT. OF WAY CHECKED _____
 CADD FILE NAME _____


STR. NO.	C146	C159	C116	C113	C34	C115	C111	C117	C112	C114	C35	C36	C118	C123	C120	C37	C122	C119	C124	C121	
STATION	146+25.00	146+50.00	146+77.44	146+77.44	146+87.44	146+87.44	146+87.44	146+97.44	146+97.44	147+07.18	147+81.07	148+77.00	148+77.00	149+83.10	149+83.10	149+93.10	149+93.10	149+93.10	149+93.10	150+03.10	150+03.10
OFFSET (ft)	32.70 RT	20.70 LT	21.55 LT	33.20 RT	13.00 LT	22.30 LT	33.20 RT	22.91 LT	33.20 RT	54.00 RT	13.00 LT	13.00 LT	32.70 LT	32.20 LT	20.70 RT	13.00 LT	31.71 LT	21.20 RT	30.21 LT	20.70 RT	
TYPE	INL-A	INL-A	INL-B	INL-B	MH-A	INL-B	INL-B	INL-A	INL-B	INL-A	MH-A	MH-A	INL-A	INL-A	INL-A	MH-A	INL-B	INL-B	INL-A	INL-A	
DIA. (ft)	2.00	2.00	3.00	3.00	5.00	3.00	3.00	2.00	3.00	2.00	5.00	4.00	2.00	2.00	2.00	4.00	3.00	3.00	2.00	2.00	
F&G	T3	T3	T3	T3	T1-CL	T3	T3	T3	T3	Special	T1-CL	T1-CL	T3	T3	T3	T1-CL	T3	T3	T3	T3	
RIM EL.	697.42	697.31	697.15	696.97	697.37	697.13	696.96	697.12	696.97	696.83	698.12	696.77	696.36	695.43	695.61	695.82	695.43	695.60	695.46	695.61	
INV. N					694.35		693.57			694.08	689.96	693.58			691.92	691.89	692.74				
INV. S					690.43	694.37			693.99		690.96		693.66		691.59	692.62		692.80			
INV. E	694.71	694.60	694.44	694.22	689.00	694.39	693.94			690.41	690.83		692.73	692.90	691.59	692.70	692.80	692.80	692.75		
INV. W			694.46	694.28	688.98	694.39	693.98	694.42	693.97	689.39	690.81				691.32	692.70	692.80	692.80	692.75	692.90	

PIPE NO.	C159	C116	C113	C115	C111	C117	C112	C114	C35	C36	C118	C37	C123	C120	C122	C119	C124	C121	C38
SIZE (in)	12	12	12	12	15	12	12	12	30	18	12	18	12	12	12	12	12	12	15
LENGTH (ft)	25.00	7.00	7.00	5.00	42.00	8.00	7.00	21.00	89.00	92.00	17.00	112.00	8.00	8.00	16.00	31.00	8.00	8.00	68.00
TYPE/CLASS	1 / IV	1 / IV	1 / IV	1 / IV	1 / A	1 / IV	1 / IV	1 / IV	2 / III	2 / A	1 / IV	1 / IV	1 / IV	1 / IV	1 / IV	1 / IV	1 / IV	1 / IV	1 / IV
T.B.F. (cu yd)	1.8	0.5	0.6	0.5	14.3	0.6	0.7	3.9	109.0	74.6	1.7	38.6	0.6	0.7	2.3	4.4	0.6	0.7	16.0

STR. NO.	C125	C38	C127	C129	D3	E1	E2	C167	D1	D2	C163	D4	C164	C39	C131	C130	C132	C133
STATION	150+45.00	150+64.71	150+64.71	150+64.71	59+78.00	59+78.00	60+08.00	60+08.00	60+08.00	60+62.00	61+07.50	61+07.50	61+07.50	62+50.00	62+50.00	62+50.00	62+50.00	62+50.00
OFFSET (ft)	34.05 LT	13.00 LT	24.55 LT	20.70 RT	19.70 LT	19.70 RT	20.20 RT	12.00 LT	20.20 LT	20.16 LT	12.00 LT	26.23 LT	19.70 RT	12.00 LT	38.20 LT	23.49 LT	32.55 RT	47.44 RT
TYPE	INL-A	MH-A	INL-B	INL-A	INL-A	INL-A	INL-B	MH-A	INL-B	INL-A	MH-A	INL-A	INL-A	MH-A	INL-A	INL-B	INL-B	INL-A
DIA. (ft)	2.00	4.00	3.00	2.00	2.00	2.00	3.00	4.00	3.00	2.00	4.00	2.00	2.00	5.00	2.00	3.00	3.00	2.00
F&G	Special	T1-CL	T3	T3	T3	T3	T3	T1-CL	T3	T3	T1-CL	T3	T3	T1-CL	Special	T3	T3	Special
RIM EL.	695.00	696.18	695.91	695.96	697.09	697.09	697.18	697.40	697.18	697.35	697.75	697.43	697.53	698.75	695.82	698.48	697.84	695.19
INV. N		691.91	691.96	693.23	694.29	694.29		693.76	693.96	694.55	693.29	693.35	693.53	691.97	691.04	691.61	691.80	691.86
INV. S	692.05	692.22	691.94				693.93	693.96	693.96	694.55	693.35	693.43	694.58	691.04	691.61	693.03	692.84	691.80
INV. E								693.78	693.96	694.55	693.43	694.58	694.73	691.61	693.03	692.84	691.80	691.86
INV. W		691.89					693.90	693.81	693.91	693.53	693.53	694.58	694.73	692.30	693.03	692.97	691.78	691.86

PIPE NO.	C125	C127	C129	D3	E2	E1	D1	D2	C167	D4	C164	C163	C39	C131	C130	C132	C133	C40
SIZE (in)	15	15	12	12	12	12	12	12	12	12	12	12	24	12	12	18	18	15
LENGTH (ft)	20.00	9.00	31.00	28.00	28.00	29.00	5.00	52.00	95.00	11.00	29.00	90.00	44.00	13.00	7.00	41.00	13.00	67.00
TYPE/CLASS	1 / IV	1 / IV	1 / IV	1 / SS WM	1 / SS WM	1 / IV	1 / IV	1 / SS WM	1 / IV	1 / IV	1 / IV	2 / A	2 / III	1 / IV	2 / III	2 / III	1 / A	1 / IV
T.B.F. (cu yd)	1.0	1.9	4.4	2.6	2.9	4.1	0.7	4.8	18.4	1.7	4.4	34.5	46.2	0.4	4.5	31.0	0.5	22.8

NOTE:
 1. FOR F&G SHOWN AS SPECIAL, SEE DETAIL ON MISCELLANEOUS DETAIL SHEET.



REVISIONS	
NAME	DATE

CITY OF DANVILLE, ILLINOIS
 WINTER AVENUE RECONSTRUCTION
 PROPOSED STORM SEWER SCHEDULES
 STRUCTURES AND PIPES
 WINTER AVENUE
 BOWMAN AVENUE

SCALE: NTS
 DRAWN BY: CGF
 DATE: 12/21/06
 CHECKED BY: ACW