

WORK ZONE PAVEMENT MARKING REMOVAL SCHEDULE

FROM STATION	TO STATION	LENGTH (FEET)	NO. OF STRIPES	WIDTH (INCH)	COLOR	LANE EDGE	QUANTITY (SQ FT)
STAGE 2 FROM PREVIOUS STAGES							
148+12.00		13.2	1	24	WHITE	STOP BAR	26.4
148+12.00	148+50.00	38.0	1	4	WHITE	LEFT	12.7
148+12.00	148+50.00	38.0	2	4	YELLOW	CENTER	25.3
148+12.00	148+50.00	38.0	1	4	WHITE	RIGHT	12.7
56+21.67	58+40.00	218.3	1	4	WHITE	LEFT	72.8
56+21.67	58+40.00	218.3	2	4	YELLOW	CENTER	145.6
56+21.67	60+00.00	378.3	1	4	WHITE	RIGHT	126.1
60+00.00	61+75.52	180.5	1	4	WHITE	RIGHT	60.2
62+03.00	63+50.00	152.5	1	4	WHITE	RIGHT	50.8
69+02.93	69+50.00	47.1	1	4	WHITE	LEFT	15.7
69+02.93	69+50.00	47.1	2	4	YELLOW	CENTER	31.4
63+50.00	69+50.00	600.0	1	4	WHITE	RIGHT	200.0
69+50.00	73+39.29	389.3	1	4	WHITE	LEFT	129.8
69+50.00	73+39.29	389.3	2	4	YELLOW	CENTER	259.5
69+50.00	73+39.29	389.3	1	4	WHITE	RIGHT	129.8
STAGE 2 TOTAL							1298.8
STAGE 3 FROM PREVIOUS STAGES							
56+21.67	58+40.00	218.3	1	4	WHITE	LEFT	72.8
56+21.67	58+40.00	218.3	2	4	YELLOW	CENTER	145.6
56+21.67	56+88.90	67.2	1	4	WHITE	RIGHT	22.4
69+02.93	69+50.00	47.1	1	4	WHITE	LEFT	15.7
69+50.00	73+39.29	389.3	1	4	WHITE	LEFT	129.8
70+35.00	73+39.29	304.3	2	4	YELLOW	CENTER	202.9
72+95.61	73+39.29	43.7	1	4	WHITE	RIGHT	14.6
STAGE 3 TOTAL							603.8
STAGE 4 FROM PREVIOUS STAGES							
147+43.53	147+55.00	11.5	1	4	WHITE	LEFT	3.8
147+43.53	147+55.00	11.5	2	4	YELLOW	CENTER	7.6
147+43.53	147+55.00	11.5	1	4	WHITE	RIGHT	3.8
147+55.00		13.0	1	24	WHITE	STOP BAR	26.0
56+98.15	57+78.16	80.0	1	4	WHITE	LEFT	26.7
56+98.15	60+00.00	301.9	2	4	YELLOW	CENTER	201.2
56+98.15	60+00.00	301.9	1	4	WHITE	RIGHT	100.6
61+05.13	61+75.74	76.4	1	4	WHITE	LEFT	25.5
60+00.00	61+63.73	163.7	2	4	YELLOW	CENTER	109.2
60+00.00	63+50.00	350.0	1	4	WHITE	RIGHT	116.7
62+02.52	62+43.69	46.6	1	4	WHITE	LEFT	15.5
62+13.74	63+50.00	136.3	2	4	YELLOW	CENTER	90.8
63+50.00	69+50.00	600.0	2	4	YELLOW	CENTER	400.0
63+50.00	69+50.00	600.0	1	4	WHITE	RIGHT	200.0
71+75.76	73+39.29	163.5	1	4	WHITE	LEFT	54.5
69+50.00	73+39.29	389.3	2	4	YELLOW	CENTER	259.5
69+50.00	73+39.29	389.3	1	4	WHITE	RIGHT	129.8

FROM STATION	TO STATION	LENGTH (FEET)	NO. OF STRIPES	WIDTH (INCH)	COLOR	LANE EDGE	QUANTITY (SQ FT)
STAGE 4 PRIOR TO FINAL SURFACE COURSE							
141+50.00	145+00.00	350.0	1	4	WHITE	LEFT	116.7
141+50.00	145+00.00	350.0	2	4	YELLOW	CENTER	233.3
141+50.00	145+00.00	350.0	1	4	WHITE	RIGHT	116.7
145+00.00	147+69.00	269.0	1	4	WHITE	LEFT	89.7
145+00.00	147+69.00	269.0	2	4	YELLOW	CENTER	179.3
145+00.00	147+69.00	269.0	1	4	WHITE	RIGHT	89.7
147+69.00		13.0	1	24	WHITE	STOP BAR	26.0
148+19.00		13.2	1	24	WHITE	STOP BAR	26.4
148+19.00	151+00.00	281.0	1	4	WHITE	LEFT	93.7
148+19.00	151+00.00	281.0	2	4	YELLOW	CENTER	187.3
148+19.00	151+00.00	281.0	1	4	WHITE	RIGHT	93.7
151+00.00	156+35.00	535.0	1	4	WHITE	LEFT	178.3
151+00.00	156+35.00	535.0	2	4	YELLOW	CENTER	356.7
151+00.00	156+35.00	535.0	1	4	WHITE	RIGHT	178.3
54+20.00	60+00.00	580.0	1	4	WHITE	LEFT	193.3
54+20.00	60+00.00	580.0	2	4	YELLOW	CENTER	386.7
54+20.00	60+00.00	580.0	1	4	WHITE	RIGHT	193.3
60+00.00	61+75.42	181.2	1	4	WHITE	LEFT	60.4
60+00.00	61+62.06	162.1	2	4	YELLOW	CENTER	108.0
60+00.00	61+72.75	177.6	1	4	WHITE	RIGHT	59.2
62+02.20	63+50.00	153.2	1	4	WHITE	LEFT	51.1
62+13.42	63+50.00	136.6	2	4	YELLOW	CENTER	91.1
62+00.29	63+50.00	155.1	1	4	WHITE	RIGHT	51.7
63+50.00	69+50.00	600.0	1	4	WHITE	LEFT	200.0
63+50.00	69+50.00	600.0	2	4	YELLOW	CENTER	400.0
63+50.00	69+50.00	600.0	1	4	WHITE	RIGHT	200.0
69+50.00	73+39.29	389.3	1	4	WHITE	LEFT	129.8
69+50.00	73+39.29	389.3	2	4	YELLOW	CENTER	259.5
69+50.00	73+39.29	389.3	1	4	WHITE	RIGHT	129.8
STAGE 4 TOTAL							6250.9
TOTAL							8153.5
USE							8154

TRAFFIC CONTROL AND PROTECTION SCHEDULE

LOCATION	QUANTITY (L SUM)
PROJECT LIMITS	1
TOTAL	1

DATE _____ BY _____
 SURVEYED _____
 PLAN _____
 REVISIONS _____
 CHECKED _____
 NO. _____
 NOTE BOOK _____
 RT. OF WAY CHECKED _____
 CAD FILE NAME _____

REVISIONS		CITY OF DANVILLE, ILLINOIS WINTER AVENUE RECONSTRUCTION TEMPORARY TRAFFIC CONTROL PLANS SCHEDULES
NAME	DATE	
SCALE: NTS	DATE: 12/21/06	DRAWN BY: MLS CHECKED BY: MBF