

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8178	05-00016-01-PV	MORGAN	31	3
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	21
20200100	EARTH EXCAVATION	CU YD	3,105
20800150	TRENCH BACKFILL	CU YD	327
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	52
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	52
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	52
25200100	SODDING	SQ YD	4,184
25200200	SUPPLEMENTAL WATERING	UNIT	125
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	85
28000400	PERIMETER EROSION BARRIER	FOOT	600
28000500	INLET AND PIPE PROTECTION	EACH	40
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	12,246
35101400	AGGREGATE BASE COURSE, TYPE B	TON	71
35501308	HOT-MIX ASPHALT BASE COURSE 6"	SQ YD	10,740
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	10
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	240
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	2,402
40600300	AGGREGATE (PRIME COAT)	TON	49
40600895	CONSTRUCTING TEST STRIP	EACH	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	269
40600990	TEMPORARY RAMP	SQ YD	495
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	1,644
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C" N50	TON	1,009
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	57
42001300	PROTECTIVE COAT	SQ YD	2,018
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	416
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	25
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	21,544
42400800	DETECTABLE WARNINGS	SQ FT	200
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	224
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	427
44000600	SIDEWALK REMOVAL	SQ FT	8,378
50105220	PIPE CULVERT REMOVAL	FOOT	678
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	200
56106400	ADJUSTING WATER MAIN 8"	FOOT	40
56106500	ADJUSTING WATER MAIN 10"	FOOT	60
56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	40

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
56300300	ADJUSTING WATER SERVICE LINES	FOOT	40
56400100	FIRE HYDRANTS TO BE MOVED	EACH	2
56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	5
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	2
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	5
60238500	INLETS, TYPE A, WITH SALVAGED FRAME AND GRATE	EACH	2
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1
60240370	INLETS, TYPE B, WITH SALVAGED FRAME AND GRATE	EACH	2
60255500	MANHOLES TO BE ADJUSTED	EACH	23
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2
60255900	MANHOLES TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	2
60260100	INLETS TO BE ADJUSTED	EACH	1
60260500	INLETS TO BE ADJUSTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	28
60266600	VALVE BOXES TO BE ADJUSTED	EACH	18
60266900	VALVE BOXES TO BE MOVED	EACH	2
60500060	REMOVING INLETS	EACH	1
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	4,828
61139800	STORM SEWERS, SPECIAL 4"	FOOT	50
61139900	STORM SEWERS, SPECIAL 6"	FOOT	50
61140000	STORM SEWERS, SPECIAL 8"	FOOT	50
67100100	MOBILIZATION	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	236
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	1,280
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	193
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	85
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	715
78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	1,280
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	193
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	85
X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	218
X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	112
XX000856	MAILBOX REMOVAL AND RELOCATION	EACH	4
Z0002800	BARRICADES	FOOT	56
Z0074600	TRAINEES	HOURLY	1000
Z0013798	CONSTRUCTION LAYOUT	L SUM	1

• SEE SPECIAL PROVISIONS  
 Δ SPECIALTY ITEMS  
 + Y080

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

WEST VANDALIA ROAD  
SUMMARY OF QUANTITIES

DATE: DECEMBER, 2006

DRAWN BY JCW  
CHECKED BY JRB

NOTE: ALL ITEMS ARE UNDER CONSTRUCTION TYPE CODE 1000