

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	JEFFERSON	17	3

- 724/821
- (14Z)TS-4;(14&1)RS-3

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
				1000-1A	Y031-1F	Y025
				90% FEDERAL 10% STATE	TRAFFIC SIGNALS 90% FEDERAL 10% STATE	90% FEDERAL 10% CITY
31100300	SUB-BASE GRANULAR MATERIAL, TYPE A 4"	SO YD	106	106		
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SO YD	95	95		
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	533	419		114
40600300	AGGREGATE (PRIME COAT)	TON	9	7		2
40600855	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N105	TON	21	18		3
40600990	TEMPORARY RAMP	SO YD	356	356		
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	455	352		103
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	162	162		
44000100	PAVEMENT REMOVAL	SO YD	95	95		
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	5043	4862		181
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	275	231		44
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	92	92		
44000600	SIDEWALK REMOVAL	SO FT	162	162		
44200150	PAVMENT PATCHING, TYPE IV, 12 INCH	SO YD	30	30		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3438	3438		
60603800	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6. 12	FOOT	92	92		
67100100	MOBILIZATION	L SUM	1	1		
70100330	TRAFFIC CONTROL AND PROTECTION, STANDARD 701426	L SUM	1	1		
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1	1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1		
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70102800	CHANGEABLE MESSAGE SIGN	CAL MO	1.5	1.5		
70300100	SHORT TERM PAVEMENT MARKING	FOOT	3325	3325		
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	121	121		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1748	1386		362
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	876	876		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	233	233		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1107	1107		
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	121	121		
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1748	1386		362
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	876	876		
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	233	233		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	80	80		
80300100	LOCATING UNDERGROUND CABLE	FOOT	60		60	
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	27		27	

* SPECIALTY ITEMS

Rev.

Rev.

1/30/2007
c:\p\c\j\m\l\p\98991\98991.mxd
50,2793 / IN
barnhartk