

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	**	JEFFERSON	17	9

- * 724/821
- ** (142)TS-4;(14&1)RS-3

PAVEMENT MARKINGS SCHEDULE

LOCATION STATION TO STATION	THERMOPLASTIC PAVEMENT MARKING LETTERS & SYMBOLS (WHITE)	THERMOPLASTIC PAVEMENT MARKING LINE 4" (WHITE SKIP-DASH)	THERMOPLASTIC PAVEMENT MARKING LINE 4" (WHITE SOLID)	THERMOPLASTIC PAVEMENT MARKING LINE 4" (DOUBLE YELLOW)	THERMOPLASTIC PAVEMENT MARKING LINE 4" (WHITE PARKING)	THERMOPLASTIC PAVEMENT MARKING LINE 6" (WHITE SOLID)	THERMOPLASTIC PAVEMENT MARKING LINE 24" (WHITE SOLID)
	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
IL 37							
STA 38+20 TO STA 38+71.5		34.1		103			
STA 38+71 (STOP BAR)							35
STA 39+57 TO 42+65 (RT PARKING LINES)					115		
STA 39+57.8 (STOP BAR)							35
STA 39+57.8 TO 42+75.4		211.7		635.2			
STA 39+79 TO 42+65 (LT PARKING LINES)					107		
STA 42+76.5 (STOP BAR)							32.6
STA 43+48.3 (STOP BAR)							33.4
STA 43+48.3 TO STA 43+82		22.5		67.4			
JORDAN ST							
STA 0+42.6 (WEST STOP BAR)							23
STA 0+42.6 TO STA 0+93.6 (WEST)			51	102			
STA 0+46 TO 0+92.5 (RT PARKING LINES)					21.5		
STA 0+43.4 (EAST STOP BAR)							24
STA 0+43.4 TO STA 0+90.0 (EAST)			47	93.2			
BROADWAY (IL 15EB)							
STA 45+08.9 TO 46+39.6 (2 - LANE DIVIDER LINES)				261.4			
STA 45+21.1 TO STA 46+11.6					37.5		
STA 45+39 @ 17.3 FT LT (COMB. LEFT ARROW)	26						
STA 45+14 @ 5.2 FT LT (ONLY & THRU ARROW)	32.3						
STA 45+39 @ 5.2 FT RT (COMB. RT ARROW)	26						
STA 46+39.6 (STOP BAR)							
STA 47+18.9 TO 47+78.6 (2 - LANE DIVIDER LINES)				119.4			
STA 47+46 @ 14 FT LT (ONLY & LT. ARROW)	36.4						50
IL 37/JORDAN ST INTERSECTION							
CROSS WALK						436	
IL 37/BROADWAY INTERSECTION							
CROSSWALK						439.6	
SUB TOTALS							
	120.7	268.3	478.8	1000.8	281	875.6	233
GRAND TOTALS							
	121		2029			876	233

1/24/2007
 ca:\proj\jefferson\98991\p1.mxd
 8:00AM / IN
 B:\C:\HW