

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	*	WILLIAMSON	8	6
STA.		TO STA.		
FED. ROAD DIST. NO. - ILLINOIS		FED. AID PROJECT		

*09_PAVEMENT_PRESERVATION_EY07

SUMMARY OF QUANTITIES

				FAP 331 (IL 13) EASTBOUND LANES	
				RURAL	
				100% STATE	
				MICROSURFACING	
				WILLIAMSON	
				1000	
CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	QUANTITY	
X0325223	FIBER ASPHALT	POUND	39890	39890	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6818	6818	
X4400105	MICRO-SURFACING, 1 PASS, TYPE 2	SQ YD	75746	75746	
67100100	MOBILIZATION	L SUM	1	1.0	
70100330	TRAFFIC CONTROL AND PROTECTION, STANDARD 701426	L SUM	1	1.0	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1.0	
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	3834	3834	
70300210	TEMPORARY PAVEMENT MARKING-LETTERS ^{AND} SYMBOLS	SQ FT	109.2	109.2	
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	37735	37735	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	13718	13718	
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS ^{AND} SYMBOLS	SQ FT	109.2	109.2	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	37735	37735	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	229	229	

* SPECIALTY ITEMS

PLOT DATE = 1/23/2007
 FILE NAME = c:\pva\pva\98995\7-01000100.dwg
 PLOT SCALE = 8294.175 / IN.
 USER NAME = mcorcoran