

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	*	WILLIAMSON	8	7
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
*09_PAVEMENT_PRESERVATION_EY07				

RESURFACING SCHEDULE

LOCATION - STATION TO STATION	LENGTH	ROADWAY WIDTH	ROADWAY AREA	SHOULDER WIDTH	MICRO-SURF., 1 PASS, TY. 2	BIT. MATLS. (PR. CT.)	FIBER-ASPHALT	NOTES	
	FOR INFORMATIONAL PURPOSE ONLY								
	(FT)	(FT)	(SQ YD)	(FT)	(SQ YD)	(GAL)	(POUND)		
IL 13 - STA. 341+00 TO STA. 510+00									
341+00 TO 477+36	13636.0	24.0	36363		36363	3273	22,268	MAINLINE	
STR. NO. 100-0071 OMIT STA. 477+36 TO STA. 479+45									
479+45 TO 510+00	3055.0	24.0	8147		8147	733	4,438	MAINLINE	
LT 396+50 TO 402+00	550.0	12.0	733		600	54		LT TURN LN	
LT 493+50 TO 499+05	555.0	12.0	740		606	55		LT TURN LN	
RT 396+50 TO 402+00	550.0	12.0	733		600	54		RT TURN LN	
LT 340+00 TO 510+00	16606.0		11007	6.0	10,941	985	6,602	LT SHLD	
RT 340+00 TO 510+00	16556.0		18600	10.0	18,489	1664	6,582	RT SHLD	
					75,746	6818	39,890		

* Right shoulder width varies 10' to 14' from Sta. 423+80 to Sta. 437+50 for portable scales area.

PAVEMENT MARKING SCHEDULE

STATION TO STATION	THPL PAVEMENT MARKING				TEMPORARY		NOTES
	4 INCH WHITE	4 INCH YELLOW	4 INCH SKIP-DASH YELLOW	LETTERS & SYMBOLS	4 INCH	LETTERS & SYMBOLS	
	FOOT	FOOT	FOOT	SQ FT	FOOT	SQ FT	
IL 13 - STA. 341+00 TO STA. 510+00							
341+00.0 TO 477+36.0	13,586.0	13,436.0	3,409.0		30,431.0		Edge line
OMIT STRUCTURE STR. NO. 100-0071 - STA. 477+36 TO STA. 479+45							
479+45.0 TO 510+00.0	2,970.0	2,970.0	764.0		6,704.0		Edge line
LT 398+50.0 TO 400+50.0	200.0				200.0		L+ Turn Ln
LT 398+50.0			20.8			20.8	Only
LT 398+78.0			15.6			15.6	L+ Turn Arrow
LT 495+75.0 TO 497+75.0	200.0				200.0		L+ Turn Ln
LT 495+75.0			20.8			20.8	Only
LT 496+03.0			15.6			15.6	L+ Turn Arrow
RT 398+50.0 TO 400+50.0	200.0				200.0		R+ Turn Ln
RT 398+50.0			20.8			20.8	Only
RT 398+78.0			15.6			15.6	R+ Turn Arrow
SUB-TOTALS	17,156.0	16,406.0	4,173.0	109.2	37,735.0	109.2	
TOTALS		37,735.0		109.2	37,735.0	109.2	

PLOT DATE = 1/23/2007
 FILE NAME = c:\pavement\98995\98995.dwg
 PLOT NAME = 09PAV07 / IN
 USER NAME = jharriso